SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1905, by Munn & Co.]

Vol. XCIII.—No. 4. ESTABLISHED 1845. | NEW YORK, JULY 22, 1905. | 8 CENTS A COPY. $3.00 A YEAR.



Length, 800 feet. **Beam,** 88 feet. **Molded Depth,** 60 feet. **Maximum Draft,** 36 feet. **Displacement,** 43,000 tons. **Horse-power of Four Turbines,** 75,000. **Speed,** 25 knots.

These Are the First Transatlantic Liners to Adopt Passenger Elevators. Because of the Great Size of the Ships, the Average Stateroom Will Be 50 Per Cent Larger Than in the Existing Fast Passenger Steamers.

SECTION THROUGH ONE OF THE GREAT 25-KNOT CUNARD LINERS.—[See page 66.]



SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO., - - Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

One copy, one year for the United States, Canada, or Mexico $3.00
One copy, one year, to any foreign country, postage prepaid. £0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845).....$3.00 a year
Scientific American Supplement (Established 1876)..... 5.00 "
American Homes and Gardens..... 3.00 "
Scientific American Export Edition (Established 1878)..... 3.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.
MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, JULY 22, 1905.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are *sharp*, the articles *short*, and the facts *authentic*, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

FACING AND TRAILING SWITCHES.

The facing switch is one of the most fruitful causes of railroad accidents in this country. The switch is an absolutely necessary feature in railroad operation; for without it it would be impossible for trains to be moved from the main line onto sidings and into freight yards. The unquestionable peril which attaches to switching arrangements, especially on lines of fast passenger traffic, is not inherently necessary. It may be removed entirely by a reconstruction, the cost of which would be cheap in comparison with the great security that would be gained by the lines that made the change. There are two methods by which a train running on the main line of traffic can be moved on to a siding. One is by what is known as a facing-point switch which, when it is set for the siding, enables the train to turn out without stopping, as it merely has to slow down sufficiently to take the rather sharp curve without risk of derailment. If, by mistake or malice, the switch has been "left open," a fast train, traveling at a higher speed than that at which it is possible for it to take the siding safely, will jump the switch, and a derailment and probable wreck will ensue. The "trailing switch," on the other hand, opens backward in the opposite direction to the traffic, that is to say, a train taking the siding at a trailing switch, must run entirely past it and then back up into the siding. If a switch of this kind be left open by mistake or malice, a train will run through it without any risk of derailment, the flange of the wheels automatically thrusting the switch open as the train passes.

The facing switch becomes dangerous only in the presence of carelessness or malicious interference. It can be used with safety as a part of a system controlled from a signal tower, or in positions where it is under full observation and surveillance at all times. For use at remote country stations on the main line of a railroad that runs fast expresses at all hours of the day and night, the facing-point switch is a distinct menace to the safety of passengers. In such cases it should be abolished and the trailing switch substituted. It is, of course, too much to ask our railroads to make this change at every station; but there are a large number of insignificant sidings where it should be made, and made at once. There would be some delay at times, due to long freight trains having to run entirely past the switch before backing into the siding; but on a well organized road, this matter, like the other difficult problems of transportation, could be properly adjusted.

BELOW THE BELT.

It is semi-officially stated by the Russian Admiralty that the battleships "Navarin," "Borodino," "Alexander III.," and "Kniaz Souvaroff" "turned turtle" during the battle of the Sea of Japan and went down with all hands. Of all forms of destruction that can befall a warship, this is the most terrible, for it involves the all but total loss of the ship's company. In a recent letter to the London Times Sir Nathaniel Barnaby, the well-known naval constructor, draws attention to the fact that the capsizing of these large ships has been attributed to some fault in their design, and he refers to statements which he has made in a book written a few years previously, to the effect that the modern ship of war, whether of the protected or armored type, was in danger of capsizing when wounded under water, to an extent unknown fifty years ago. He had also claimed that the increased risk of capsizing before sinking of the wounded ship of war of to-day was not peculiar to any particular class of ships or to any particular navy.

We are of the opinion that the capsizing of the Russian ships was probably caused by hits below the water-line belt of armor. The possibility of such hits being made was greatly increased by the fact that there was a heavy sea running, and that in rolling the ships must at times have rolled the bottom edge of the armor entirely out of the water. Furthermore, it has happened in naval engagements of this war fought in smooth water, that vessels have suffered from shot holes below the water. In reply to our inquiry as to how this happened, one of the captains of the Port Arthur fleet informed us that shells fired from long range and striking the water a short distance from the side of the ship, would pass through the water and strike below or near the bottom edge of the belt. A case of this kind occurred on the battleship "Czarevitch," and several other vessels were similarly damaged. It cannot be urged that in the battle of the Sea of Japan the shot-holes which admitted water to these ships were made through the unprotected ends; for with the exception of the "Navarin," the belt armor was carried entirely from stem to stern.

The talented French designer of the "Borodino," "Alexander III.," and "Kniaz Souvaroff" paid particular attention to the under-water defensive qualities in these ships, and the fact that they were protected with a 9-inch belt of Krupp armor renders it probable that, at the range at which the earlier phases of the battle were fought, the belt armor itself was not penetrated. It begins to look as though the water-line armor will have to be carried down deeper, and it may be that it will also be carried to a higher level above the water line. This means bigger ships and larger displacement; but it will probably have to be done. Another change which may be necessary to prevent the capsizing of badly hulled warships is the elimination of longitudinal bulkheads, or rather, we should say, the provision of means for allowing an unrestricted flow of the water in any damaged compartment from side to side of the ship. The three ships of the "Borodino" class above mentioned carried a vertical wall of armor from end to end of the ship at a distance of about 12 to 15 feet inboard. It is possible that the water that entered on the sides exposed to the fire of the enemy collected between the outside hull and this inner wall of armor, and quickly brought the ship into the capsizing condition. It is true that in order to trim the ship provision is made for flooding compartments; but it may well be that in the confusion of a terrible sea fight like this, the necessary knowledge as to what compartments need to be flooded to preserve an even keel may be wanting to the very men whose duty it is to open the valves or control the pumps.

THE SECOND CITY IN THE WORLD.

The incomplete census figures indicate that the population of New York is now just under 4,000,000, or, to be exact, 3,987,154. The probabilities are that Manhattan and the Bronx alone will be found to have a population of 2,378,696. It is interesting to go back and compare the population of New York in the successive stages of its growth with that of to-day. The first federal census, taken in 1790, shows that the population was 33,131. In 1800 it had risen to 60,515, and in 1810 it was 96,373. In the next twenty years it more than doubled, having reached 202,589 in 1830. By the middle of the century it had passed the half million mark. Thirty years later, in 1880, it had again more than doubled, the population being 1,206,293. From 1900 to 1905 New York has grown from 3,437,000 to 3,987,154, or at the rate of over 100,000 a year. The standing of New York among the big cities of the world is shown by the following figures: London comes first with 4,536,641 people, and next to New York are Paris, with 2,714,008; Berlin, with 1,888,848, and Chicago with 1,698,575. Then follow Vienna, Canton, Tokio, and Philadelphia, all of which have over 1,000,000 inhabitants, the last named having 1,293,697 in the census of 1900.

As to the possibility of New York city becoming the largest city in the world, there is no indication that London will lose the first place for many decades to come, for within the metropolitan and city police limits that city contains 6,581,372 souls, this being the population of what might be called Greater London. To put it another way, London's "Manhattan" contains 4,613,812 souls as against New York's Manhattan population of 2,127,602; while her Greater London has 6,581,372 people as compared with Greater New York's population of just under 4,000,000. The rate of growth, however, is faster in New York than in London and if the present rates should continue, it will only be a question of time before the largest city in the world will be found in the Western Hemisphere.

FASTEST LONG-DISTANCE RAILROAD RUN.

The publication of the high speeds that were made by the eighteen-hour trains in their preparatory tuning-up runs, has re-awakened interest in the question of fast long-distance runs. One of the most interesting contributions to the subject is that of the English railway expert, Mr. W. M. Acworth, who, during his visit to the International Railway Congress in this country, was enabled to take notes of some very fast work by the famous American expresses that run during the summer months from Philadelphia to Atlantic City. These trains are scheduled to travel at average rates of 66.6 to 68.1 miles an hour, and on the occasion of Mr. Acworth's trip, a speed of 80 miles an hour was maintained continuously for a distance of 30 miles. In a recent article on the subject, in the London Engineer, Mr. Acworth raised the question whether anything like this performance had been accomplished on the Great Western Railroad's record run from Bristol to London. This was made last year by one of the Ocean Mail Specials from Plymouth to London, when the distance from Exeter to Bristol was made at the rate of 70.5 miles an hour and from Bristol to London at the rate of 71.5 miles an hour, the whole distance of 193¾ miles being thus covered at an average speed of 71 miles an hour. Mr. Rous-Martin, who was on the engine during this performance, states that a speed of 80 miles an hour was sustained, with virtual continuity, for 73 miles consecutively, the only time that the speed fell below 80 being while water was being taken from a water trough, the resistance of which reduced it to 75 miles an hour. During the fastest run recorded by Mr. Acworth on the Philadelphia-Atlantic City line, a distance of 55½ miles was covered in 42½ minutes. The same distance was covered during the Great Western's run in 42 minutes, which brings the average up to 79.3 miles an hour. The American and English runs for this distance were, therefore, almost identical in speed; but it is claimed that the remarkable feature of the Great Western engine's work was the long distance (193¾ miles) during which the high speed was maintained, and the fact that the engine which did the work was of a somewhat old-fashioned type. The American load was heavier; but on the other hand, the American engine was able to exercise double the tractive power of the English single-wheel type; and it is claimed, very properly, that the wonderful speed achieved on this road proves that for running fast trains, of which there are so many in England, the single driver type is admirably adapted.

The United States possesses in its 18-hour trains from New York to Chicago the fastest long-distance trains, the Pennsylvania maintaining an average speed of 50.3 miles for 905.4 miles, and the New York Central covering 959.4 miles at the rate of 53.3 miles an hour.

TESTING THE TOURING CARS.

The automobile tours which have just been carried out under the direction of one of the leading national associations have done much toward emphasizing the necessity of good roads for both touring and business transportation purposes; and one of these tours—that to the White Mountains for the Glidden trophy—has also demonstrated anew the cheapness of transportation by auto as opposed to that by rail, especially when a pleasure journey is being undertaken. With a touring car carrying five persons, from the results obtained on the tour, it appears that each person can be carried for about one-fourth the rate charged by the railroads, or in other words, for one-half cent a mile. This rate, however, is for transportation on good roads and exclusive of tire repairs. On poor roads the cost of fuel will be found to be augmented somewhat; but the greatest drawbacks are the low average speed possible to be maintained and the discomfort the passengers are obliged to undergo. In the western 500-mile tour from Chicago to St. Paul, so much rain was encountered that the roads were well-nigh impassable, and many of the tourists shipped their cars by rail after completing half of the journey. No less than eleven machines, however, made the journey under the most trying conditions. Instead of a pleasure tour, the automobilists made an endurance run of which they may well be proud. Among the cars that completed the journey were three White steam machines, three Knox air-cooled cars, a Pierce, a Packard, a Rambler, a Jackson, a Reo, and an Adams-Farwell air-cooled machine with a revolving-cylinder motor. These cars were three representative types of American machines, and they demonstrated once again the capability of the domestic car even under the worst weather conditions and roads that America is able to produce.

In the Glidden tour, thirty-four representative machines started from New York on July 11, and of these some twenty-eight reached Mt. Washington on July 14. A feature of this tour was the employment of a Packard and a Knox truck to transport the baggage of the tourists. These machines made very good daily runs, and generally delivered the baggage at its destination sooner than if it had been sent by express. Some interesting data on the cost of long-distance hauling based on their performances should be available at the conclusion of this 1,000-mile tour.

Within three years, at most, practically worthless land, so heavily charged with injurious salts as to be unfit for any form of agriculture, may be reclaimed to grow any ordinary field crop. The method of doing this is simple; and the expense involved is such that the work may in many instances be economically undertaken by individual, corporate, or State initiative. The total expense of reclamation, taking everything into consideration, is but a small fraction of the enhanced value.

ROMAN TEXTILE MANUFACTURES.

BY ALEX DEL MAR, M.E.

Weaving is an art of the highest antiquity. In the Vedas, VI, ix, 2, the Rishi declares that he knows "neither the warp nor the woof of religious rites." In the Iliad, the Bible, the Zendavesta, in the earliest writings of every nation of antiquity, it is distinctly described. Whether man learnt it from the weaver-bird, or it grew out of platting, we know not. Its origin is plainly Oriental; and a loom of apparently the most elementary form is still used in India; and what is yet more strange, it is capable of producing the most delicate tissues known to the art. There the village weaver stretches his warp between two bamboo rollers, one of which is suspended from a tree, while the other is fastened to the earth by wooden pins driven into the turf. The earth also forms his seat, and two holes dug into it accommodate his legs. The shuttle which carries the woof is shaped like a netting-needle, and being somewhat longer than the breadth of the fabric, it is employed also as a batten, to shove the threads of the woof close up to each other.

From the Orient, the names of staples, tissues, and fabrics enable us to trace the art of weaving into Asia Minor, Egypt, and Europe. In the Augustan age the woolen industry had been established in the Levant for upward of a thousand years; the weaving of silk, both from unraveled Indian tissues, from Oriental yarns, and from the threads of native silk-worms, had been practised in the island of Cos for over 500 years. The weaving of cotton cloths belongs practically to the Alexandrian age; while the manufacture of linens in Rome was comparatively new, it having but recently been imported from Egypt. The Roman manufacture of other textiles, such as hemp, esparto, and asbestos, though interesting, was comparatively unimportant.

We are indebted to Ovid, Met. vi, 53, for an account of the woolen manufacture; dressing the wool; picking or teasing, combing, and carding it; spinning the yarn with distaff and spindle; winding, or forming the thread into clues, and dyeing. The earlier looms, like their Indian prototypes, were perpendicular, hence the warp was called *stamen* and the woof *subtemen*, and the shuttle, *radius*. The looms, the fulling-mills (for cleaning, scouring, and solidifying the cloth) and the dyeing-works, were run by water power; and although the principal works were in the city of Rome, numerous others were established in all parts of the empire, especially in Spain, Gaul, and Britain. Among the woolen fabrics were *phrygians*, a coarse shaggy cloth, made in the Asiatic provinces, and out of which the Roman tailor fashioned the brown lacerna, or great-coat, a garment with a hood, like the French military tunic of the present day. A shorter overcoat or cape, also with a hood, was called penula. It was made of a hairy cloth called *gausapa*. Another fabric called *frigus*, was like the Scotch and Irish frieze of modern times. A fabric similar to our broadcloth was called *rasa*, or smooth. *Virgata* was a striped cloth; *scutulata*, a spotted or figured tissue; *galbina*, a green or grass-colored fabric, worn by women; *palla* meant black or gray mourning-goods, etc. Among the other products of the Roman woolen looms were damasks; embroideries made on the loom, sometimes with gold and silver threads and figures; tapestries, shawls, bunting, rugs, and carpets. The bunting was used for signal flags and for the colors carried by contestants in the chariot races. These last were organized in four companies, the Greens, Reds, Blues, and Whites; and they were championed with such *esprit de corps* and zeal that even the women became partisans, and wore silk ribbons of their favorite colors.

Before that great influx of the precious metals which followed the conquests of Scipio, Titus, Mummius, Lucullus, Sylla, Pompey and Cæsar, the linen industry, like many other industries of Rome, consisted of importing the fabric from other countries, in this instance from Egypt. The culture and treatment of flax and its manufacture into a variety of fabrics had grown to considerable perfection in that country; and until Rome became a great center of capital, but feeble efforts were made to transplant this great branch of trade. With the reign of Augustus came that unity of the empire and universal peace which afforded security and assurance to its overflowing treasuries; and among the industries adopted or greatly extended was the culture of flax and manufacture of linen, either in Italy or in the Roman provinces, of which, of course, Egypt was now one. Among the various fabrics mentioned in the works which are left to us are damask tablecloths, table-napkins, and handkerchiefs, *sudaria*. A fine linen cloth from Sidon was called *sindon;* although Martial says that the same or similar stuff came also from Egypt. A twilled linen fabric, or diaper, had long been worn in Asia Minor, Egypt, and Greece. This industry was now taken up by the Romans and introduced into Italy and several of the western provinces. Linen sails for ships were also made in various parts of the empire.

The Roman costume consisted chiefly of the woolen toga and tunic; the shirt, *camisia;* and leg-cloth, *tibialia*. The overcoat, mittens and cap, *pileus*, were only for cold weather. Of these various articles, the shirt and leg-cloth were of linen, sometimes, also, the tunic. The purple border to the toga was a survival of the purple thread of the Hindu. The latter was made from the staple of the purple cotton plant; the former was dyed with the famed murex of Tyre.

Flax was cultivated successfully in many parts of Asia Minor, including Palestine, and in most of the Greek states. Pausanias wrote that "the fine flax which is produced in Elea, is a very proper subject of admiration; for it is not to be found (in such perfection) in any other part of Greece. . . . But the fine flax (produced) within Elea, is not inferior in tenuity to that of the Hebrews; while it is less yellow." After being retted in running water for about a month, it was taken out, dried, and made ready for extracting its fibers. For this purpose a bunch of it was taken in the hand, laid upon a table, and beaten with a wooden instrument. It was afterward drawn forcibly over the angle of the table, in order to free it from fragments of the stem. Then it was heckled or passed through iron combs, beginning with coarse and ending with finer ones. In this condition the fibers were free and ready for spinning into threads or yarn. The various machines and devices for retting, heckling, spinning, and weaving this staple, though derived from the older industry of hemp-manufacturing, were much improved by the Romans, who paid great attention to the details of the linen trade and exported their products to numerous places in Asia Minor and Europe.

The cotton plant and cotton fabrics are mentioned as of Indian origin by Herodotus, 450 B. C. The culture was brought westward by the followers of Alexander and Seleucus, and established in Egypt under the Ptolemies. After the battle of Actium, Egypt became a Roman province, and both the cotton fields and cotton mills of that country fell into the hands of Roman capitalists. The earlier Roman name for cotton was probably *byssus*, because its fabrics resembled linen ones, just as in England it is still called "cotton-wool," because the staple looks like bleached wool. The later Roman name was *gossypion*. *Xylon* rather meant the cotton-tree; though it was sometimes used to mean the staple. It is well known, of course, that cotton-fabrics have been found in Egyptian graves older than the Ptolemaic period; but this does not prove that they were made in Egypt, any more than a silk fabric found in an American grave of the present day would prove it to be American, the probability, amounting almost to certainty, being that it was manufactured in Europe or Asia. Cotton fabrics, however, do not appear to have become popular in Italy. The finer cotton tissues still came from India, and were very expensive; while the coarser ones were hardly so well suited to the Roman climate as linens. Before the Egyptian cotton manufacture became sufficiently improved in quality and cheapened in price to command the Italian market, it fell into the hands of the Arabians, and Rome lost the control of what was destined to become the greatest of the textile industries.

Silk, though it had been imported from the Orient for many centuries, and cultivated to a small extent in some of the Greek islands, was nevertheless so scarce during the Augustan period as to command its weight in gold. The common name for it was *serica*, or *vestis serica*, sometimes *bombycina*, from *bombyx*, the silk-worm. The Roman ladies wore a broad ribbon around the waist called *strophium*, which served for the modern bodice, or stays. This ribbon or sash was made of silk. Soft clinging stuffs of silk for the *stola* were next worn; and finally the *palla* came to be made of the same expensive material. Its use was forbidden to men. Elagabalus is said to have been the first male Roman who wore a robe of pure silk; and Aurelian to have refused the empress, his wife, a garment of this fabric, on account of its exorbitant price. Yet in Pliny's time, which was much earlier, the importation of Indian silks, to be unraveled by Roman girls in order to work up the threads with woolen yarns and so make from them new and less expensive fabrics, appears to have become an important industry; from which it would seem that stories about the parsimony of distinguished people are not always to be relied upon for historical accuracy.

Hemp is an East Indian plant which was brought into Europe probably during the first Buddhic period. Herodotus mentions a species so closely resembling flax that the Thracian women made fabrics from it which could hardly be distinguished from linen. The best hemp known to the Romans was grown at Alabanda, on the banks of the Meander, and the next best at Mylasa, near the Gulf of Jasus, both of these places being in Asia Minor. In Italy it was chiefly cultivated in the territory of the Sabines, a very ancient people. Hemp was at first employed for the ropes and rigging of ships. Moschion, about 200 B. C., records the use of hempen ropes for rigging the ship "Syracusia," built for Hiero II. some fifty years previously. Twine, hunting nets, and finally coarse fabrics, for household use, were successively made of it. The various machines and devices for retting, heckling, combing, spinning, and weaving this staple were applied to flax when that textile came to be manufactured in Rome.

Human hair was also employed as the basis of several Roman industries, chiefly by wig-makers and jewelers. A Roman matron's wig, of a beautiful brown color, full, rich, glossy, and ending in a heavily plaited chignon, is preserved among the curiosities of the York Museum. Although 1,800 years old, it can scarcely be distinguished from a modern peruke of the most fashionable design.

The grass fibers employed by the Roman weavers, such as esparto, corn-husks, and straw, the latter for ladies' hats, were as numerous as they are at the present day. Many of them were also used for stuffing mattresses and upholstering furniture—for example, corn-husks, wool-flocks, and grasses of various sorts.

Asbestos, like many other substances which formed the bases of Roman industries, was originally obtained from India, but afterward from Arcadia. The Greeks gave it the name of *asbestinon*, which means inextinguishable; while the Romans called it *vivum*, or live (linen). They made table-napkins of it, which could be cleansed during the meal, by throwing them for a minute or so into the fire. Shrouds for the dead were also made of this substance, though it was so excessively dear that only the wealthiest people could afford to purchase it. In the year 1702 there was dug up near the Nævian Gate at Rome a funeral urn, in which human remains of the classical period were found wrapped in asbestos cloth, many yards in length. This interesting example of Roman textile art is still preserved in the Museum of the Vatican.

SCIENCE NOTES.

That common simile in which the various divisions of science are represented as branches of the tree of knowledge, is a grotesque survival of a time when neither trees nor science were understood. No simile is perfect or even approximately correct, but one better than the tree and its branches for the origin and relationships of any inductive science is that of a river, rising from various and often obscure sources, growing in size and importance as it proceeds both from the springs within its own bed and by the entrance and contributions of tributary streams, and finally pouring its substance into the mighty ocean of accumulated human knowledge.

Some of the arts are nearer to the welfare of man than others, and the same is true of the sciences. Two arts, however, lie very near human welfare, and if we were called upon to give up all of the arts but two there would be little difference in choice as to which two should be preserved. The one most important would be the art of agriculture and the next the art of healing. Man first of all must be nourished, and next to this, kept in health. We might look forward to a time when lawyers would disappear. We might even grow so perfect as to be able to do without ministers of the gospel. Even the histrionic art might be abandoned, and yet mankind be reasonably happy. But strike down agriculture and you strike a blow which is fatal; banish the healing art and you leave man to the ravages of disease.

Enormous as is the annual loss which may now be fairly charged to insects, it would undoubtedly be vastly greater if such pests were left absolutely unchecked and no efforts were made to limit their operations. Were it not for the methods of controlling insect pests, resulting from the studies of the Bureau of Entomology and of the official entomologists of the various States, and the practice of these measures by progressive farmers and fruit-growers, the losses from insects would be greatly increased. Familiar illustrations of savings from insect losses will occur to anyone familiar with the work in economic or applied entomology in this country. The cotton worm, before it was studied and the method of controlling it by the use of arsenicals was made common knowledge, levied in bad years a tax of $30,000,000 on the cotton crop. The prevention of loss from the Hessian fly, due to the knowledge of proper seasons for planting wheat, and other direct and cultural methods, results in the saving of wheat to the farm value of from $100,000,000 to $200,000,000 annually. Careful statistics show that the damage from the codling moth to the apple is limited two-thirds by the adoption of the arsenical sprays, banding, and other methods of control, representing a saving of from $15,000,000 to $20,000,000 in the value of this fruit product alone. The existence and progress of the citrus industry of California were made possible by the introduction from Australia of a natural enemy of the white scale, an insect pest which was rapidly destroying the orange and lemon orchards, this introduction representing a saving to the people of that State of many million dollars every year. The rotation of corn with oats or other crops saves the corn crop from the attacks of the root worm to the extent of perhaps $100,000,000 annually in the chief corn-producing regions of the Mississippi Valley. The cultural system of controlling the boll weevil is already saving the farmers of Texas many millions of dollars, and, in fact, making the continuance of cotton growing possible; and scores of similar illustrations could be cited.

THE SMALLEST WORKING MODEL OF A TRIPLE-EXPANSION ENGINE.

The model of the engine illustrated in the accompanying engraving is, perhaps, the finest piece of skilled work of its kind that has ever been brought to our attention. The little engine, which is of the marine triple-expansion type, was built by Mr. Robert Bunge, of New York city, an expert on machinery, who has made the construction of miniature machines his pastime.

The engine here shown measures 3½ inches across the bedplate, and stands 3¼ inches from the bottom of the bedplate to the top of the cylinder covers. Every part is perfect. It is even equipped with the link reversing motion. With a steam pressure of 100 pounds, 7,260 revolutions per minute are made, turning a screw 2½ inches in diameter by 7 inches pitch.

The high-pressure cylinder is 5-16 of an inch in diameter, the intermediate cylinder 8-16, and the low-pressure cylinder 10-16 of an inch. Something of the wonderful refinement and precision with which this model has been made may be gathered from the fact that the valves are of the regular piston type for all cylinders, and measure five, seven, and nine thirty-seconds of an inch in diameter. The shaft, the cranks, and crank-pins are all turned from one piece of steel, which in itself is a rather neat piece of work.

The eccentrics are split, and are exact miniature duplicates of those used on engines actually in service. The smallness of the studs and nuts used to hold down the cylinder covers is almost incredible. The nuts used in the construction of the model are for the most part a fraction less than 1-16 of an inch in diameter; and yet each is perfectly hexagonal in shape. The studs are a little less than 1-32 of an inch in diameter, and are threaded at both ends, one end screwing into the machine, and the other receiving the nuts.

The crossheads are made of steel, and are fitted with brass shoes that can be taken up whenever wear occurs. The steam pipe is 1-8 of an inch in diameter, and the exhaust is 3-16 of an inch in diameter. The maker may well claim for this model that it is the smallest triple-expansion engine in the world. To appreciate its diminutive perfection at its true worth, it must be seen in actual operation.



THE SMALLEST WORKING MODEL OF A TRIPLE-EXPANSION ENGINE.

An accompaniment of the introduction on shipboard of surface condensation, which was at first supposed to be a result of it, but which as a matter of fact was not, was a tremendous increase in the corrosion of the boilers and a shortening of their life. This was especially noticeable in the tubes which, as the thinnest part of the boilers, give out first. All sorts of theories were advanced to account for it, some of which we can now see to have been utterly ridiculous. Probably one of the most fanciful was that which regarded the boiler and condenser as forming a gigantic galvanic battery, the copper condenser tubes forming one pole, and the boiler the other. The real facts were developed as a result of the investigation by the Admiralty Committee on boilers in the 70's, which showed that boiler corrosion was simply rusting and had been due to gross but unintentional neglect. It had been a very common practice, particularly in naval boilers, when they were not in use, to blow out the water and take off the manhole plates "to let them air." It was this "airing" which caused the corrosion. Now when boilers are laid up, they are filled with water which is made slightly alkaline, and this effectually prevents corrosion.

A LIGHTHOUSE OF REINFORCED CONCRETE.

BY EMILE GUARINI.

A lighthouse of reinforced concrete has recently been constructed at the mouth of the Boug, a river flowing into the Black Sea. It is situated 115 feet from the river shore and serves, with an existing but lower lighthouse, to guide vessels in the direction of the maritime canal excavated in the river and connecting with the sea the city of Nikolaew, which is situated about 100 versts from the mouth of the Boug.

The construction of the lighthouse of reinforced concrete was decided upon after a comparative study of other projects, some calling for the use of bricks and others of iron. Reinforced concrete was found to give a saving of about 40 per cent with an equal stability.

The system consists of a tower of which the walls are from 5 to 10 inches in thickness and are constructed upon a foundation, likewise of reinforced concrete, and imbedded in the sandy soil to the depth of 10 feet.

The stability is assured by the weight of the sand resting upon the foundation. The maximum of pressure upon the ground is about 7 pounds to the square inch. The coefficient of stability at the level of the ground is 4.

The frame is formed of round iron bars of 1¼-inch diameter. The calculation is so made that it shall be able, without the concrete, to resist a wind pressure of 55 pounds to the square foot. The height up to the lantern is 110 feet.

The diameter of the tower is 21 feet at the base and 6½ at the lantern.

The lantern is divided into two parts, one of which serves as the dwelling of the keeper, while the other is arranged for the lighting apparatus.

For the concreting there was constructed an external wooden wall having exactly the form of the tower. The concreting was done from the interior. The concrete was formed of sea gravel, coarse sand, and Portland cement in the proportion of 1:2:4.

The concreting was done in winter, in the space of two weeks, with the aid of heat in the interior. The external woodwork required two months for its construction.

The external woodwork was removed in the spring of 1904, and, up to the present, although the tower has been submitted to the action of very high winds, no evidence of strain has been detected.

The cost of the structure, exclusive of the lighting apparatus, was about $6,000.

The project, the calculations, and the execution are due to M. N. Piatnitsky, engineer of ways of communication, and the architecture is the work of M. A. Bauchnikow, likewise engineer of ways of communication.



Brick Lighthouse. Iron Lighthouse. Concrete Lighthouse. Armored Concrete Lighthouse.

A COMPARISON OF THE CONSTRUCTION OF SEVERAL TYPES OF LIGHTHOUSES.

Report on the Sleeping Sickness.

A valuable report concerning the dreaded "sleeping sickness," which infests the East Africa Protectorate, has been prepared by Dr. C. A. Wiggins, principal medical officer at Nairobi. The disease, he finds, is propagated by the tsetse fly; this insect is found in trees or bushes near the lake coast line. The difficulties and dangers of poisoning by this pest during a journey in these parts are exemplified in Dr. Wiggins's account of the passage of the Yala swamp. This is an extensive expanse of huge masses of papyrus, or large tracts of black mud, with stagnant, ill-smelling water, both reaching to the waist. Papyrus, it was observed, does not shelter the flies. In Mageta Island an epidemic had raged, and out of 500 inhabitants not one survived, and the place is now deserted.

A NOVEL GYRATING STEAM ENGINE.

A new form of steam engine, with which a constant thrust is obtained on the driven shaft, is shown in the accompanying illustration. The engine is the invention of Mr. Frederick Egge, of Bridgeport, Conn., and it will be found particularly useful for any service where a powerful, compact, and light-weight engine that can be instantly reversed is desired, such as for hoisting work and for automobiles. As can be seen in the illustration, the engine consists of four horizontal cylinders placed symmetrically around a central tube containing, near its right-hand end, ports opening into the cylinders (one port for each). The piston-rods are fitted with ball and socket joints at both ends. Their outer ends are connected to a sort of spider set at an angle with the transversely-placed disk on which it is mounted. The thrust of the piston rods on the arms of this spider tends to push it off the periphery of the disk, but as the spider is firmly secured to the disk, this is revolved instead, and the spider goes through a gyrating motion as it is successively driven by each of the four pistons. The spider is mounted on and pinned to a short rod having a bearing at its upper end near the periphery of the disk and at its lower end in a block on the extremity of a small central shaft that actuates the rotary valve for supplying live steam to and carrying off the exhaust steam from all four cylinders. The gyrating movement of the spider causes this rod (which has a universal joint near its lower end) to make one turn to every revolution of the disk, and thus the valve also is driven at the same speed as the disk. The valve consists of a sleeve having two sets of ports—one set for running in either direction—as well as a suitable exhaust port. The lever on the side of the engine slides the valve laterally, and instantly reverses the engine. This feature is the result of the constant thrust at an angle of 30 deg. obtained from one or another of the four pistons.

The photograph which we reproduce is that of a working model designed to show the use of the motor as a hoisting engine. It could also be applied to an automobile by direct attachment to the rear axle with a bevel or spur gear drive. An engine of this type can be built of very light weight, and so should be useful in all cases where a portable motor is needed.



A NOVEL GYRATING STEAM ENGINE.

THE NEW BRITISH YARD STANDARD.

BY HERBERT T. WADE.

During the past year the Standards Department of the British Board of Trade has been engaged in studying and verifying a new yard standard, in which have been incorporated all the refinements made possible by the modern science of metrology. The present imperial standard or legal yard of Great Britain is a bronze or gun-metal bar of rectangular section legalized by Act of Parliament in 1855. The true or legal yard is taken as the distance at 62 deg. F. between two fine lines on the surfaces of two gold plugs that are sunk in wells or holes near the ends so that their surfaces lie in the median or neutral plane of the bar where any effects of flexure are reduced to a minimum. A number of copies of this standard bar were made when it was constructed and one of them, No. 11, was given to the United States government, and is now in the fire-proof vault of the National Bureau of Standards at Washington. It has twice been taken to England for comparison with the British standards, and for many years served as a standard of length for the United States. A study of the various bronze standards, however, showed that they were not absolutely invariable and that their length was likely to be altered some minute but appreciable amount by molecular and other changes taking place in the alloy of which they were formed. In fact, the unsuitableness of bronze for a prototype standard was recognized at the time when the construction of an international standard meter was proposed in 1872, and the commission determined on an alloy of platinum and iridium, not only for the international prototype, but also for the various national standards which were to be similar in size, form and composition. In making these standards, it was necessary to use a material that resembled as closely as possible the original platinum meter of the Archives, but also its composition should be such that it would be free from oxidation and possess as well the requisite strength, elasticity, and other mechanical characteristics. These meter bars when completed represented the most careful and accurate workmanship, so that when the two standards allotted to the United States were received by the government, it was only a brief space of time before they were adopted by executive order as the national fundamental standards of length, from which the yard or common unit was to be derived by using the ratio 3600/3937 specified in the Act of July 28, 1866. Thus the British bronze standard yard was displaced as a standard of length in the United States by the platinum-iridium meter of the International Commission, despite the fact that Anglo-Saxon weights and measures were and are universally employed.

Convinced a few years ago of the necessity of constructing a new copy of the imperial standard yard, the Standards Department of the Board of Trade, under the direction of Mr. H. J. Chaney, superintendent, decided to employ such a material as would best answer the requirement of resistance to oxidation, hardness, density, permanence, elasticity, etc., and select such a form as should be considered best in the light of actual experience with standards of length and the developments of metrological science. These matters had been most thoroughly discussed and investigated at the time of the construction of the international metric standards, when it was realized that such materials as gold, platinum, iron, or even rock-crystal, for various reasons, were quite unsuitable. Accordingly, it was determined to employ an alloy of 90 per cent platinum with 10 per cent iridium. This was possible by the adoption of a peculiar cross section of X shape devised by M. Tresca, of the French committee, whereby sufficient strength and rigidity were obtained without the employment of an undue amount of metal such as would render the cost prohibitive or the bar of unwieldy mass. Furthermore, the platinum-iridium alloy expands but little with an increase in temperature, while its surface can be given a high polish so that the lines marking the standard distance could be engraved directly on its surface. These international standards had not only proved eminently satisfactory in their use at the Bureau of Weights and Measures and in the various national laboratories, but no essential improvements could be suggested, so that the British metrologists concluded that they could do no better than to copy the composition and their form in constructing their new standard yard. Thus they would have a standard whose constants would be known not only independently, but also in terms of the International Prototype Meter. Fortunately, they were able to obtain one of a series of bars made from an ingot of the specified alloy which was cast at the Conservatoire des Arts et Métiers at Paris for the use of the Bureau International des Poids et Mesures. In 1902 this bar was polished and adjusted at the laboratory of the Société Genevoise pour la Construction d'Instruments de Physique at Geneva, and was then sent to the International Bureau of Weights and Measures at Sevres, near Paris, where a meter and a yard were traced on the bar by M. J. Rene Benoit, the director. This was accomplished with the dividing engine of the bureau, and the same general means and methods were employed as were used when the standard meter bars were constructed and graduated. The construction and form of the new standard will be apparent on reference to the accompanying illustration, which shows clearly the X or Tresca section. The rigidity of the bar is manifest from its design, while provision is made whereby the neutral or median plane coincides with the upper surface of central portion or cross bar on which the lines are traced, reducing to a minimum any effects of flexure caused by inequalities of the supports. On this surface parallel with the axis of the bar are traced two fine lines, 0.2 millimeter distant from each other, and across these is another fine line which marks one extremity of the standard length, the latter being measured between two such lines, points being taken which are included between the longitudinal lines, the general appearance when seen under the microscope being as shown in the accompanying engraving. In the new British standard one such transverse line marks the beginning for both the meter and the yard, while at the opposite end of the bar there are similar sets of lines to indicate the limits of each. In short, the new standard is practically a standard meter with a yard marked on it, and thus the British Standards Office now has on a single bar a determination of the value of both of these fundamental units of length as given by the officials of the International Bureau in terms of the international standards, and also, after the conclusion of the present investigation of the bar, its value in terms of the Imperial Standard, which doubtless will be legalized in some form or other. According to the officials of the bureau the new British standard when referred to the International Prototype Meter at 0 degree Centigrade is too long by 2.9 microns or 29 parts in ten million, while the yard marked when referred to the yard standards and equivalents of the Bureau was too long by 0.000226 inch when reduced to 62 deg. F., the British standard temperature. After its determination and study at the Bureau, the new bar was then carried to London, where it has been the subject of a most careful investigation by the officials of the Standards De-

British Iridio-Platinum Yard Standard Showing Cross-Section. The Bar is in the Position it Occupies in the Comparator.

The Standard Turned on Its Side and Showing the Two Defining Lines (Magnified) on the Neutral Surface of the Bar.



THE NEW MICROSCOPIC COMPARATOR OF THE BRITISH STANDARDS OFFICE.

partment, having been compared directly with the national or Imperial Standard in an elaborate series of experiments. The result of the preliminary observations when computed and reduced was that the platinum-iridium standard was too long by 0.000227 inch, but the investigation has not as yet been concluded and this value may be changed. The research, however, brought out many interesting points about the British standards of length and their degree of accuracy. The Imperial Standard yard is legally defined to have its true length when measured at the temperature of Fahrenheit's thermometer, but there was and is no legal standard of the Fahrenheit thermometer, and the original temperature measurements employed in determining the bar were made with mercurial thermometers which vary 0.3 deg. Fahrenheit plus and minus. As the length of any solid such as a bar is continually varying with changes in temperature, it is of course impossible to determine linear values with precision unless the temperature is known with a degree of accuracy corresponding to the other measurements. Consequently, the British observers were forced to follow the example of the International Bureau and modern physicists generally reduce all their readings to the scale of the gas thermometer containing hydrogen. This also involved a careful study of the thermometers, new and old, so that in the present determinations the temperature effects could be considered and corrected for with the greatest possible precision. The comparisons were made at the Standards Office, Old Palace Yard, Westminster, and the old Sheepshanks comparator used when the Imperial Standard was constructed was employed in some of the comparisons, as well as a Troughton and Simms comparator which was built in 1870. But these instruments were considered to be somewhat below the standard demanded by modern metrological science, so accordingly a new comparator was built capable of the greatest accuracy and embodying all refinements that scientific thought could suggest and precise workmanship execute. As the object of a comparator is to determine as accurately as possible the difference in the length of two or more standards, its essential characteristics are two micrometer microscopes mounted on heavy masonry pillars, so as to be free from all vibration, and some suitable mechanical device to permit the scales to be placed successively below the microscopes in the same position. The distance between the two microscopes remains constant during the comparison, and the bars to be compared are placed below them, so that the cross-wires of the microscopes can bisect the fine lines of one of the standards. Then when this standard is replaced by the other under exactly similar conditions, by means of the micrometers the cross-wires can be brought to bisect its lines, and the difference in length be determined. Of course, means must be provided for carrying and moving the standards, for regulating the temperature and keeping it uniform, illuminating the surfaces of the bars, avoiding vibration and other disturbances, and providing for many other conditions demanded in exact measurement. The construction and action of a modern comparator can best be appreciated by reference to the illustration, which shows the new instrument of the British Standards Office, which is essentially the same as the comparator of the Bureau International, and involves the most improved devices. It is mounted on a deep foundation of concrete, which rests on rubble over sand. On the concrete are placed three slate slabs, two of which carry massive blocks of Yorkshire stone, forming the two pedestals for the microscopes, while the third or center slab carries the heavy cast-iron frame on which are the rails for the carriage carrying the scales. To prevent any movements of the observers being communicated to the apparatus, there is an air space surrounding the foundation to a depth of five feet. On the tops of the stone pedestals are bolted heavy cast-iron supports or brackets for the microscopes, whose objectives are about 95 millimeters above the bars. The latter are carried in a trough on a carriage capable of a transverse movement beneath the microscopes, and also so arranged that the height of the bars can be adjusted by micrometer screws which raise or lower the trough. The latter is double-walled, and water kept in circulation by an electrically-driven agitator flows in the intervening space, and causes a constant temperature to be maintained. The bars themselves rest on rollers in the trough, so that they are free to expand or contract with any change in temperature. The micrometers are of the ordinary type, where a system of cross-wires arranged in the focal plane of the objective can be moved by means of an accurately cut screw with a divided head moving in a nut. By means of a linear scale placed in the field of the microscope, the value of the space traversed by the cross-wires during one revolution of the screw is ascertained, and fractions of a revolution can be determined from the graduated head and its vernier. The illumination of the surface of the bars is also important, and the method adopted is to send light from a small incandescent lamp into the microscope tube, and by means of a thin polished plate of glass inclined at an angle of 45 degrees reflect it onto the lines of the bar. With this new instrument it is believed that the highest accuracy can be secured, and that the British Imperial yard can be defined in a more satisfactory manner, as well as be represented by a more permanent and accurate standard.

THE MAMMOTH CUNARD LINERS.

It is many years since there was the same amount of interest attached to the building of a new liner for transatlantic service as is shown in the two turbine-driven Cunarders which are now under construction, one at Swan & Hunter's yard on the Tyne, and the other at the John Brown Company's works, Clydesdale.

This interest is due to the extreme size, the high speed aimed at, and the novel character of the motive power. To find a parallel to the interest in these vessels we have to go back to the year 1889, when the Inman and International Company brought out the first twin-screw ships to be seen in the Atlantic service, the "City of New York" and "City of Paris." Furthermore, it is realized by the general public that these new Cunarders represent the determination of Great Britain to win back the Atlantic record, which was lost several years ago to the "Kaiser Wilhelm der Grosse," and which has subsequently been easily retained by those other fine German ships, the "Deutschland" and the "Kaiser Wilhelm II."

It is known that the new Cunarders are to be the largest ships ever built; but it is not generally realized how very much larger these ships are to be than any of the huge liners which now excite our wonder by their great proportions. The increased dimensions are shown in the accompanying table, which includes the largest of the ocean liners that have been built of late years; and on comparing the Cunarders with the largest of the existing fast passenger ships, the "Kaiser Wilhelm II.," we find that she is longer by 94 feet than that vessel; that she has 7½ feet more molded depth; that she has 16 feet more beam; that her designed horse-power is nearly twice as great; that her displacement is 13,000 tons more; and her sea speed will be 1½ knots greater. Furthermore, in view of the fact that turbine engines invariably develop a horse-power greatly in excess of the contract, it is possible that on her trial she may make 26 knots an hour, or 2½ knots more than the record speed of the "Kaiser Wilhelm II."

THE BIG STEAMSHIPS OF THE WORLD.

	Length over all, in feet	Beam, feet.	Depth, feet.	Displacement.	Horse-Power.	Speed.
Great Eastern	692	83	57½	27,000	8,000	14.25
Lucania	625	65	42	19,000	30,000	22.01
Oceanic	704	68	49	28,500	28,000	19.50
Deutschland	686	67	42	23.000	37,500	23.5
Baltic	725	75	49	40,000	18,000	16.25
Kaiser Wilhelm II.	706	72	52⅛	30,000	40,000	23.5
Turbine Cunarders	800	88	60	43,000	75,000	25

It was not the original intention to make these vessels of such extreme proportions. They grew to the dimensions ultimately adopted, as the result of the elaborate studies that were made, both at the towing tank and at the designing board. The first tentative plan called for a vessel 700 feet in length. This grew to 720 feet, and finally to the present overall length of 800 feet. The beam is 88 feet measured over the skin plating, or 87 feet 6 inches to the outside of the frames; the plating, by the way, being 1½ inches in thickness, which, on the lap, will bring it to a total thickness of 3 inches on each side. The plated depth is 60 feet, which may be compared with the 42 and 49 feet molded depth of such ships as the "Deutschland" and "Oceanic," the plating being, in this vessel, carried up one deck higher. This increase is rendered necessary by considerations of the longitudinal girder strength of the ship as a whole, and is one of the means by which the necessary shearing strength is obtained. The extreme draft is 36 feet; but this, of course, can only be availed of when the new Ambrose Channel into New York harbor shall have been fully dredged out. The government has promised sufficient depth in this channel, by the time the Cunarders are ready, to enable them to come and go, drawing 33½ feet of water. On the latter draft they will displace a little over 40,000 tons, and on the full draft of 36 feet they will displace about 43,000 tons. Of the dimensions given above, the beam is the most striking, and these ships are the first to exceed in beam that accepted standard of measurement for modern steamships, the "Great Eastern."

The drawing on our front page contains the first authentic information regarding their interior structure. The double bottom, which is the most important structural element in the hull, will be 5 feet 6 inches in depth between the outer and inner shells. There will be a dead rise of 18 inches from the keel to the bilge, and the frames will decrease from 5 feet 6 inches at the keel to about 4 feet in depth where the curve of the bilge straightens into the sides. There will be about twenty longitudinal frames consisting of heavy built-up I-beam sections, extending, some of them, the full length of the ship. Our sectional view is taken at about the midship section, and it passes through one of the boiler compartments. The great width of the ship enables the Scotch boilers, which will be of the largest size, to be placed four abreast, and still leave room for large coal bunkers in the wings. There are eight decks in all. First, the Orlop deck, just above the boiler rooms, on which, in this particular part of the ship, there will be space for carrying the regular ship's stores; the deck above, known as the Lower deck, will be devoted largely to third-class passengers. A feature that will add considerably to the comfort of these passengers will be the subdivision of the space into separate staterooms. The waterline will be at the level of this deck, which will be lighted with portholes, and thus provide a large number of outside staterooms for the third-class passengers. The Main deck will be given up to first-class staterooms. The Upper deck, also, will be devoted to first-class accommodation, and on this deck will be the great dining saloon, which will extend the full width of the ship, providing a single room over 80 feet in width by 125 or more feet in length, and capable of seating over 500 people. In the center will be a large overhead well, which will extend through two decks and be crowned with a dome of cathedral glass. The fifth, or Shelter deck, completes the molded portion of the vessel, and is 60 feet above the keel. The three decks above this, known as the Bridge deck, Promenade deck, and Boat deck, are devoted to first-class passenger accommodation, and they have, on each side of the central tiers of staterooms, a broad promenade open to the weather.

How greatly these ships will exceed all others in the nature of the passenger accommodations is shown by the fact that the first-class staterooms are to be 50 per cent larger than the customary size. The total height of the ship, from the keel to the boat deck, is about 90 feet, or the height of say an eight-story building. In the presence of such dimensions, the problem of what might be called "vertical travel" becomes a serious one. On shore we have overcome it by the adoption of the elevator; and with the growth in size and steadiness of the giant passenger ships, the time has now come when the passenger elevator can be applied with perfect safety to these floating hotels. The Cunard Company was the first to incorporate the elevator in the plans for its new ships; and it may interest the readers of the Scientific American to know that the first practical suggestion of the use of the marine elevator was made in 1902 by a member of the staff of our paper to Mr. Vernon H. Brown, the general manager of the company in America, who thought so well of it, that he forwarded the suggestion to the Liverpool office with his approval of it as a practical improvement. The suggestion was adopted, and at once incorporated in the plans of the ship. There can be no question of the great convenience that will be afforded by a passenger elevator on board large steamships, and it is pretty certain to be generally adopted.

The motive power will consist of four turbines, each of a designed indicated horse-power of 18,000, which latter, by the way, is about the total horse-power of the "City of Paris" and the "City of New York," above referred to. All four turbines will be placed upon the same platform; but while the propellers of the inside pair will be located just forward of the rudder in the usual position, the propellers of the outside pair of turbines will be located forward of the inner pair, the great beam of the ship admitting of this arrangement. Although the contract horse-power is about 71,000, the boiler power is sufficient for 75,000 horse-power, and 75,000 horse-power with reciprocating engines would, according to the tank test, give a speed of 25 knots an hour. Mr. Hunter, of the firm of Swan & Hunter, where one of these ships is being built, has supplemented the tests of the tank models, constructed on a quarter-inch scale, by building a working model on a ¾-inch scale, which is 50 feet in length. He has equipped this model with turbines and four propellers, and has been making a large number of tests with propellers of every conceivable practicable type. The results of these experiments, of course, are not available outside the company, but it is sufficient to say that they are very promising for the complete success of the great ships themselves. As regards the speed of the vessels, they must show an average of 24½ knots an hour on actual voyages. Judging from the way in which the steam turbines in the British cruiser "Amethyst" ran ahead of the anticipated results, we shall not be surprised to see these vessels exceed an average speed of 25 miles an hour from port to port under favorable conditions.

Correspondence.

The Lunar Rainbow.

To the Editor of the SCIENTIFIC AMERICAN:

The article in your issue of July 8, 1905, "A Lunar Rainbow," calls to my mind a similar phenomenon witnessed by the writer several years ago, only this was on a perfectly cloudless night. It occurred about 9 o'clock P. M. I was coming over a hill, to the west of which was a deep valley. A thick bank of fog lay over the valley, and as I descended into the valley I saw the bow perfectly defined. The colors were very faint, but the whole arch was perfect. How long it was visible I could not say. W. W. RANDALL.

Sea View, Mass., July 12, 1905.

The Reasoning Powers of Animals.

To the Editor of the SCIENTIFIC AMERICAN:

I have with much interest noted the discussions in your columns as to whether animals can reason. Two letters to this effect, published June 3 and July 1, apparently attempt to establish an affirmative theory that animals actually do reason, giving as they do the story of the cat which has learned to open a door by its latch and even knob. Let me say in the name of psychology that these cats did in no way show reasoning power, but on the contrary it was an act of dumb imitation, prompted by dire necessity on the part of the animals to get inside or outside, and indeed they had ample opportunity to learn under the circumstances.

While I do not discredit the reasoning power of elephants or beavers, however limited it may be, it does not demand expert observation to decide positively that at least animals of the feline genus and some other carnivorous ones, as for instance the bear, are wholly destitute of reason. Why? In Central Park the reason is engraved in not only hard cement, but also in the nose of a cinnamon bear. This animal is fenced in, but he can easily see freedom outside, and he has long ago made up his mind to secure his freedom by walking outside of this cruel inclosure. Seeing that the broad side of the fence would bar him, the bear made for the front corner; but seeing this corner impregnable, he naturally turned toward the other unexplored corner quite undaunted. Of course, he is again disappointed, but since the first disappointment was forgotten by the shock of the second, he hopefully again returns to the said first corner, and so on, hour after hour, days, weeks, and year after year. Lions, tigers, leopards, etc., do exactly as does this bear; but I will say of this particular bear, that although he has worn deep holes in the cement floor in both corners of alternate hope and despair, his nose has become worn by his systematic swing of the head in spurning these really hopeless corners of escape. There is as yet no clear impression on the mind of this bear that his long search for freedom is really hopeless. But this undaunted bear can be convinced, as by cutting off his view of freedom without, and it would also teach us a lesson—that the difference between simple intuition and reasoning is enormously great.

What little reason exists in animals is so feeble, that the slightest intuitive activity on their part will easily hypnotize their reasoning powers. Imitation, as proved by the monkey or the parrot, and still more so by small children—just because they have a larger brain area—may become so extensive that almost all the product of reasoning minds may be faithfully memorized and imitated, although the minds engaged never themselves ever reason except to a negligible degree. ALBERT F. SHORE,

Member Am. Assoc. for Advancement of Science.

Brooklyn, July 7, 1905.

The Current Supplement.

Carl Lautenschlaeger's article on Theatrical Engineering, Past and Present, is concluded in the current SUPPLEMENT, No. 1542. Dr. A. P. Coleman writes on "Theories of World Building." Lord Blythswood's liquid-air plant for experiments at low temperatures is very fully discussed by the English correspondent of the SCIENTIFIC AMERICAN. The Berlin correspondent of the SCIENTIFIC AMERICAN writes on an electrical long-distance water-level indicator which has been used with success in Austria. A very excellent *résumé* of agricultural electro-chemistry is presented. The action of metals in the colloidal state on the evolution of infectious diseases is made the subject of a well-written article. An interesting lecture was recently delivered before the Cleveland Institution of Engineering (England) by Mr. Robert Whipple, in which various forms of thermometers and pyrometers, with some of their industrial applications, were described. Mr. Whipple's paper is published in full. Saghalien, the island which has just been captured by the Japanese, is fully described. Clive Holland writes on pictures with romantic histories. An abstract of the communication made by J. Butler Burke on his *radiobes*, apparently living bodies produced from day to day by radium, is published. The Rev. Reginald A. Gatty writes on "The Home of the Pigmies."

ARTIFICIAL FOUNTAIN AND GEYSER SPRINGS.*

BY MYRON L. FULLER.

Where springs issue in cool, transparent pools, or as streams of clear water from the rock, little can be added to their attractiveness by artificial means. In many places, however, the water of the springs seeps out slowly through the soil, the point of emergence being marked simply by a wet, grassy, or boggy place. In such cases the springs may often be transformed



Fig. 1.—HILLSIDE SPRING WITH WATERS UNCONFINED AND WITHOUT HEAD.

into attractive spots by the construction of artistic basins, rocky arbors, rustic spring houses, and other similar means. One of the most useful methods of treatment is the construction of a so-called "fountain spring," while the most interesting, in many ways, and the most puzzling to many, is the "geyser spring." Both are of simple construction and inexpensive. Under the hands of a competent landscape gardener they can be made to form an attractive addition to parks and



Fig. 2.—HILLSIDE SPRING WITH WATER BETWEEN IMPERVIOUS BEDS AND UNDER PRESSURE.

estates where the conditions are favorable, and where no water works system exists.

The common surface springs may be grouped according to their occurrence in two classes: Hillside springs and springs on flat or level land, both of which may or may not be under pressure or head. Where there is no pressure, the water cannot be made to rise naturally above its point of emergence, but when under head it will, if confined, rise more or less above the point at which it issues. Fig. 1 represents a hillside spring unconfined and without head, while Fig. 2 shows a similar spring, the water of which is confined between two impervious layers and under more or less pressure.



Fig. 3.—METHOD OF CONSTRUCTION OF "FOUNTAIN SPRINGS."

The latter only will rise if confined, but a fountain or a geyser spring can be constructed from either if sufficient fall can be had near the spring. Like the hillside springs, those occurring on level land can also be classed according to the amount of head, which will vary from just enough to bring the water to the surface to enough to make it boil strongly from the ground. To test the amount of head, it is necessary to confine the flow, which can be done in the manner outlined below for the construction of fountain springs.

Construction of Fountain Springs.—The term fountain spring is used to designate a spring which is made



Fig. 4.—METHOD OF CONSTRUCTION OF "GEYSER SPRINGS.

to rise through a pipe to a point above the surface. It may flow gently into a trough by the roadside or in the barnyard, into the sink in the kitchen, or it may, if the head is considerable, be made to throw a jet into the air, as in an ordinary fountain.

The aim in the construction of such a spring is to confine the water, and force it to rise instead of flowing out uselessly upon the ground, as in natural springs. To do this, a circular excavation should be made about the spring, the earth being removed to a depth of three to five feet, preferably until a clay or clayey sand is encountered. The excavation when completed should have the outline indicated by $e\ e^1\ e^2\ e^3$ in Fig. 3.

A bottomless barrel, $b\ b^1\ b^2\ b^3$, may then be inserted, and a pipe placed in the center with its bottom nearly level with the lower edge. Around the pipe inside the barrel are packed stones, three or four inches in diameter at the start, and gradually decreasing in size until a thickness of two feet is reached. About six inches of sand should then be inserted, to be followed by the same thickness of clay, or as clayey sand or loam as can be found. This should fill the remainder of the barrel, and should be worked in around the edges on the outside until all avenue of escape of the water, except through the projecting pipe, is cut off. The ground should then be leveled over and thoroughly tamped down.

The result of this treatment is that the water of the spring, deprived of its ordinary outlet, is forced to rise through the pipe. The height to which it will rise and the force with which it will flow depends upon its head, which is in turn dependent upon the elevation of its source. There are many instances where the water is raised into roadside troughs, and its possibilities in connection with farm and household supplies are considerable. A few owners of important springs, as at the No-che-mo Springs, Reed City, Mich., have by this or similar processes succeeded in obtaining streams which throw jets several feet in the air, making fountains of considerable beauty.

Construction of Geyser Springs.—By a geyser spring is meant one so piped that it will at certain intervals throw a jet to a greater or less height into the air, after which the water subsides and ceases flowing until the lapse of another interval, after which it again flows. To successfully construct a geyser spring, it is necessary to find a spring at some elevation above the point at which the flow is desired and but a short distance away. A spring on a steep hillside, not more than 50 feet away from the desired point of flow, and 15 to 20 feet higher, presents the most favorable conditions. It does not matter in this instance whether or not the water is under pressure at the spring.

The spring will nearly always emerge just above an impervious layer, as at *A* in Fig. 4. A little back from this point dig a small pit about four or five feet deep, and insert a barrel with the upper edge about six inches above the top of the impervious layer. Holes should be bored in the sides to admit the water just above the clay, this part of the barrel being surrounded by fine gravel, to keep the holes from clogging and to prevent clay and sand from entering the barrel. A pipe should be connected with the bottom of the barrel by a tight joint, and should lead upward sharply until about six inches below the top of the clay, or a foot below the top of the barrel, when it should be bent gradually and carried downward, at a depth sufficiently below the surface to prevent freezing, to the desired site of the fountain, when it should be bent again into a vertical position and brought to the surface. The pipe is in fact a simple siphon.

Starting with an empty barrel, the water gradually accumulates until a height equal to that of the upper bend of the siphon is reached, at which moment a flow is inaugurated, issuing at the fountain at *F*. The flow will continue until the water is exhausted from the barrel, when it will stop, only to commence again when the level of the top of the siphon is again reached. One precaution, however, is to be observed in regard to the making of the siphon; namely, the capacity of the pipe should be greater than the capacity of the spring, otherwise the flow once inaugurated will be continuous.

The height to which the water will be thrown depends primarily upon the altitude of the spring above the fountain; the higher the spring is, the higher will be the jet. A decrease in the size of the jet will also within certain limits increase the height to which it will rise.

* Published by permission of the Directors of the United States Geological Survey.

The Maiorana Telephone.

Prof. Quirino Maiorana has been engaged for some time in perfecting his hydraulic telephone, and according to a notice appearing in Industria, has succeeded in transmitting speech distinctly from Rome to London. The successful results of this experiment have been confirmed recently, when the London General Post Office was able to understand clearly whatever conversation was transmitted from Rome. The success of this experiment is the more remarkable as the telephone line Rome-Paris-London, apart from its length, includes submarine cables in the channel, so that this achievement can be said to be the most important telephone transmission ever obtained up to now.

COMPLETION OF VICTORIA FALLS BRIDGE.

BY THE SCIENTIFIC AMERICAN LONDON CORRESPONDENT.

In many ways the Victoria Falls bridge, over the Zambesi gorge in Central Africa, is an interesting piece of engineering work. In the first place, the structure can claim the distinction of being the highest bridge in the world. Again, the waters of the gorge which it spans have never been fathomed, and no one knows their depth. But the feat is deserving of more than ordinary notice, not so much on account of its engineering difficulties, but rather because the work has been carried out in the very heart of the Dark Continent. It was only fifty years ago that the gorge and the famous falls at their head were discovered by David Livingstone. Now it is not only possible to reach the Falls by rail, but to cross the Zambesi by the iron road, and proceed northward for another one hundred miles by the same train. The completion of the bridge means that another link—and the most important probably—has been forged in the great scheme proposed and started by Cecil Rhodes, namely, the Cape-to-Cairo railroad.

Before proceeding to a description of the bridge itself, a few facts about the railroad will not be inappropriate. The total distance by railroad from Cape Town to the Falls is 1,631 miles. Travelers from London are now carried right up to the Falls in twenty-one days, whereas prior to the opening of the line their transportation was a matter of months. At the Falls themselves there is a hotel where accommodation is provided for eighty guests. True, it is only a temporary building, but it will shortly be replaced by a permanent one. That tourists are now making their way to this spot in Central Africa to see for themselves the eighth wonder of the world, as the Victoria Falls have been rightly termed, is made clear after a chat with the present hotel proprietor. Last Christmas there were considerably over a hundred persons staying at the hotel, many of whom had to sleep in tents and temporary annexes, so crowded was the building itself. A large number of Americans visiting the Cape make the journey by railroad to the Falls, spending, as a rule, several days exploring the gorge and beautiful islands just above the great waterfall.

As to the Falls themselves, no attempt will be made here to describe them, with the exception of saying that they are the largest in the world, being about a mile in width and boasting of a depth of from 400 to 420 feet. After the waters of the Zambesi have plunged over the Falls, they continue their course for several miles in a comparatively narrow gorge, and it is this latter which has been bridged to carry the track of the Cape-to-Cairo railroad.

A word here may be said as to the site. It is a little way below the Falls themselves, on the borders of what is termed the "Rain Forest." During the rainy season the great volume of water dashing over the mighty chasm sends up five more or less distinct columns of spray to a height of 3,000 feet, which descends like heavy rain for an extensive area, whose limit is variable and is governed by the force and direction of the wind. This area is called the Rain Forest, and it is just within its full water confines that the bridge is located. It was Cecil Rhodes's wish that it should be so. He is said to have uttered the words: "Build the bridge where the spray from the Falls shall shower upon the trains as they pass." He also expressed the wish that a view of the great cataract may be obtained from the windows of the railroad carriages. The engineers have fulfilled the great man's wishes, and before these lines appear Rhodes's idea of the trains being drenched with spray from the Victoria Falls will have passed out of the region of poetic fancy to that of actual fact.

The bridge as it stands to-day represents a year's labor. It has been shipped from England, and erected on its remote site in this comparatively short space of time. It was only twelve months ago that the last section of the railroad reached the Falls. Until then nothing could practically be done. The gorge where the bridge has been built is some 650 feet in width and about 420 feet deep to the water level. The method adopted in building the bridge was as follows: It was built out simultaneously from each bank on the cantilever principle until it met in the center. To accomplish this, it was necessary of course to carry a large quantity of material to the other side of the stream. To get this across the river, an electric



EXCAVATING FOR THE ABUTMENTS OF THE VICTORIA FALLS BRIDGE.



Span of main arch	500 ft. 0 in.
Rise at crown	90 " 0 "
Depth of main arch at bearings	105 " 0 "
Depth of main arch at crown	15 " 0 "
Width between main arches at top	27 " 6 "
Width between centers of bearings	53 " 9 "
Batter of main arches	1 in 8
The main arch is divided into 20 bays of	25 ft. 0 in
Spans of end spans.....87 ft. 6 in. and	62 " 6 "
Widths between centers of girders	20 " 0 "
Depth of main girders	12 " 6 "
The end spans are divided into bays of	12 " 6 "
Clear width of roadway	30 " 0 "
The curve of the main arch is parabolic	
Camber of main arch at 60° F.	9 "

ELEVATIONS OF THE VICTORIA FALLS BRIDGE.



THE LATEST PICTURE OF THE VICTORIA FALLS BRIDGE OVER THE ZAMBESI GORGE.

Total length of bridge, 650 feet; height over low-water level, 450 feet.

cableway was thrown across the gorge. Communication was first established between the two banks by firing a rocket across. To the rocket was attached a line, by means of which a stronger rope was drawn across, and again a stronger one, until a 2¾-inch diameter steel-wire rope was thrown over the site. A box kite was first tried as a means of carrying a string across, but the rush of air at this spot always drove the kite in the opposite direction to that which it was intended to travel.

The 2¾-inch steel-wire rope referred to was supported at one end by a fixed tower, 36½ feet high, and at the other by a swinging post, 79 feet in length. To prevent this latter being pulled over by the cable into the gorge, a counter-weight of about sixty tons was attached to it. On the cable ran an electric machine, from which was suspended a cage, which carried men and material across. The whole was controlled by the motorman from the platform of his machine, who could raise and lower his car at will. When it is remembered that the gap between the supports of the cable measured 870 feet, and the aggregate amount of material that had to be transported across amounted to many thousands of tons, it will be seen that the cableway played no mean part in the undertaking. In addition to carrying the weight of one half of the bridge across the gorge, all the material and rolling stock required for the construction of over fifty miles of railroad were also safely conveyed across the stream by the electric cable. The car and its machinery weighed about five tons, and the maximum weight of load it carried was ten tons. When the cable was first erected, many distinguished visitors to the Falls took a journey across in the suspended carriage, including Princess Victoria of Schleswig-Holstein and Lord and Lady Roberts. The journey occupied about four minutes. The railroad company also allowed passengers to cross the stream by the cable, charging $2.50 for the trip.

The bridge, which is a combination of girder and arch, has a total length of 650 feet, and consists of three spans, 87 feet 6 inches and 62 feet 6 inches in length respectively. As already stated, it was erected from each side simultaneously. On account of the weight of the structure, about 2,000 tons, it was necessary to tie back the weight to each bank in some way until a junction was made, as the bridge then, of course, would carry its own weight. The manner in which this was done may be said to constitute one of the most interesting features of the whole undertaking. Two bore holes were sunk on each bank, 30 feet deep and 30 feet apart, and the two extremities joined together by boring through the rock. Wire ropes suspending the weight of each half of the bridge were passed down one hole, along the passage connecting the two, and out at the other, so that the weight was sustained by this solid mass of rock; and to make assurance doubly sure, a weight of 500 tons of rails was piled also on the top of the rock. It was estimated that when the two halves of the bridge were on the point of meeting in the center, there was a pull of 400 tons on each of the four corners, and as the bridge was built out toward the center, additional ropes were added to withstand the increased stress.

The curve of the main arch is parabolic, and is divided into twenty bays, each 25 feet long, and has a 9-inch camber at 60 deg. Fahr. The two side spans are divided into equal bays of 12 feet 6 inches. The bridge has a clear width of roadway of 30 feet, sufficient for a double set of rails. A close inspection of some of our photographs will reveal the presence of a huge net, which was thrown across the chasm on two steel cables, and was erected, so the contractors declared, "to catch the boys and tools should they inadvertently drop into it." In addition to a staff of about twenty-five European erectors, a hundred Kaffir boys were engaged upon the work.

Before the scheme was put in hand, there were not a few complaints in the public press, declaring that the erection of a bridge at the Falls would mar the beauty of the surroundings. To ascertain the general feeling of the visitors on the site chosen, a book was kept at the engineers' camp, and a very large majority of the opinions are favorable to it, many visitors being converted from hostility to approval on seeing the facts of the case—in fact, one guest goes so far as to say the following: "The Falls in their present position cannot possibly detract from the beauty of the bridge." It is not without interest here to note that the South African Company, which owns the land on both banks of the river, has decided to reserve a large area of the forest, extending for some six miles on each side of the Zambesi, as a public park, to be preserved forever in its natural beauty.



THE ZAMBESI RAILROAD BRIDGE COMPLETED

The contractors for the bridge were the Cleveland Bridge and Engineering Company, of Darlington, England. The whole of the plant was erected in their yards, and exhaustive tests were made with it before it was sent out. It was shipped at Middlesborough, on the River Tees, to Beira, a port on the east coast of Africa, a little south of the mouth of the Zambesi, and here transshipped to the railroad, which runs through flat, swampy country, until it rises about 4,000 feet above sea level at Umtali, and thence through Matabeleland to Salisbury and Bulawayo, and from the latter place to the Falls, a total distance of close upon 8,000 miles. The engineers for the work were Sir Douglas Fox & Partners and Sir Charles Metcalfe, Bart. One of the members of this firm, Mr. G. A. Hobson, M. I. C. E., the designer of the structure, and to whom the writer is indebted for much assistance in the preparation of this article, has left London to inspect and pass the bridge.

THE VICTORIA FALLS BRIDGE IN COURSE OF ERECTION. THE MATERIAL WAS CARRIED BY CABLEWAY.

A New Hardening Compound.

A Hungarian professor and chemist of the Brunn University claims to have rediscovered the secret of the ancient Greeks by which they were able to render mortar imperishable. The reason for the remarkable preservation and hard texture of this sealing material of the Acropolis, which is as good to-day as it was when first laid centuries ago, has always puzzled scientists and archæologists. This Hungarian some twenty-five years ago procured a piece of this flint-like mortar and ever since has been engaged upon ascertaining the secret of its manufacture. He has invented a chemical compound liquid in character and yellowish in color, to which he has given the name "zorene." The claims of this inventor are that by the application of this compound the density of nearly every description of stone, including granite, is doubled and is rendered absolutely impervious to water; it imparts to all metals the quality of resisting rust, and is a great, powerful germicide. These properties are not transient, but everlasting. Several practical tests to demonstrate the powers of the solution have been given in London. In the first instance, a piece of ordinary slag of a brittle nature after immersion in the liquid resisted a heavy blow from a hammer which before treatment had crushed the slag to powder. The same effect resulted when an ordinary brick was similarly treated. A block of Red Jarrow wood was then immersed in the solution and then placed in a bath of water for several hours. When withdrawn from the water, the wood was carefully weighed upon a delicate scale and found not to have absorbed a particle of water, testifying to the water-resisting qualities of this discovery. Two pieces of steel were then placed in the bath and after treatment were submitted to a severe ammonia test equivalent to an exposure to the outer atmosphere for five years. No trace of rust was observed on the metal. The professor has an ordinary steel table knife which was immersed in the compound six months ago and which has been exposed to the open air ever since; there is no trace of rust upon it. The professor will shortly give a lecture upon the subject before one of the scientific societies in London, and will carry out several demonstrations to substantiate the claims of his discovery.

An experiment with vacuum tubes of several kinds by Herr Hess showed that external friction of the tube, such as rubbing with the free hand, stimulates conductivity within.

ATMOSPHERIC FRICTION AS AN OBSTACLE IN LOCOMOTION.

BY DR. A. F. ZAHM, CATHOLIC UNIVERSITY OF AMERICA, WASHINGTON.

To plan a hull rationally, whether for air or water, one must know the pressure and friction at every point of its surface. Summing these for all parts of the body gives independently its head resistance and skin friction. In other words, the factors are to be studied separately, and then their aggregate made a minimum. In marine science this method has been used to advantage, but not so in the design of air-going hulls. Till recently it was supposed, even by eminent experimenters, that bodies of good form cleave the atmosphere without sensible friction. The writer, however, found that in air, as in water, friction is a chief element of resistance, and therefore endeavored to determine its laws accurately in his aerodynamic laboratory.

To measure the tangential force of free air flowing swiftly over even surfaces, various skin-friction planes were suspended inside a wind tunnel, by means of two fine steel wires. The tunnel itself, standing on the floor of the laboratory, measures 40 feet long by 6 feet square, and has a 5-foot suction fan at one end to generate the wind, and two cheese-cloth screens at the other end to straighten the inflowing air. The current steadily displaces the plane endwise an amount which is carefully measured, and serves to compute the wind force. As shown in one of the illustrations, the tunnel is sometimes narrowed, so as to increase the speed.

The planes employed were similar to those commonly used to determine the skin friction of water. They were smooth varnished pine boards about two feet wide, one inch thick, and having sharp ends, each end seven inches long, and they were steadied by appropriate guides. The planes varied in length from two feet to sixteen, all having identical prow and stern.

The main object was to determine the friction for various lengths of surface, at various velocities of wind, and to express the relations so found in the form of laws. To that end the total wind force on each plane was observed in a current at ten different speeds, from 5 to 40 feet a second. Subtracting the latter from the former, gave the friction on the straight sides of each board. These data revealed the laws sought for. Plotting the results, it was found that the friction varies with the length of surface as the power 0.93, and the velocity of wind as the power 1.85. The entire friction, F pounds, on a surface one foot wide and l feet long, is given by the numerical equation:

$$F = 0.00000778\ l^{0.93}\ v^{1.85}$$

in which v is the wind speed in feet per second. Of course, this value of F must be doubled for a material plane, since it has two sides. From the equation a table for engineers' use was computed, giving, at a glance, the skin friction for surfaces of various length, moving at all ordinary velocities of locomotion.

This much accomplished, some further experiments were made, to observe the effect of quality of surface on the tangential resistance. Practically the same friction was observed, whether the board was coated with dry varnish or wet, sticky varnish, or sprinkled with water, or covered with calendered or uncalendered paper, or glazed cambric, sheet zinc, or old English drafting paper, which feels rough to the touch. But when the plane was covered with coarse buckram, having sixteen meshes to the inch, the friction, at ten feet a second, was ten to fifteen per cent greater than for the smooth surface, and the friction increased approximately as the square of the speed.



Section Through Tunnel, Showing Form and Method of Suspension of Skin-Friction Planes.

Symmetrical Spindle Showing Length for Minimum Skin Friction.



The Pressure-Tube Anemometer



Interior of Tunnel Constructed so as to Increase the Resistance.



Exterior of Wind Tunnel, Showing the Screen Removed and the Skin Friction Planes in the Foreground.

The fact that such a variety of materials exhibit practically the same friction seems to indicate that this is a shearing force between the swiftly-gliding air and the comparatively stationary film adhering to the surface, or embedded in its pores. If, as seems to be true, there is much slipping, this means that the internal resistance of the air is less at the surface than at a sensible distance away. As the shearing strength of a gas is due to the interlacing of its molecules, owing to their rapid motion normal to the shearing plane, it may be that the diminution of shearing resistance near a boundary surface is due to the dampening, within the film, of the component of molecular translation normal to the surface.

To summarize the results attained thus far, it may be said that within the ascribed limits of size and wind speed:

(1.) The total resistance of all bodies of fixed shape and aspect is expressed by an equation of the form

$$R = a\ v^n$$

R being the resistance, v the wind speed, a, n, numerical constants.

(2.) For smooth planes of constant length and variable speed, the tangential resistance may be written:

$$R = a\ v^{1.85}.$$

(3.) For smooth planes of variable length l, and constant width and speed, the friction is

$$R = l^{0.93}$$

(4.) All even surfaces have approximately the same coefficient of skin friction.

(5.) Uneven surfaces have a greater coefficient of skin friction, and the resistance increases approximately as the square of the velocity.

On comparing the above results with those obtained by Froude for water, it is found that the equations are very similar. The exponents are nearly the same for a variety of materials, and the coefficients are to each other roughly as the densities of air and water. This fact is of considerable practical interest. For it is well known that the head resistances of any two fluids are directly as their densities; and hence, if their friction coefficients also bear nearly that ratio, the total resistances must be approximately as their densities. Thus the data obtained from water-resistance measurements may be used with fair accuracy to estimate the air resistance on various-shaped models. However, this must be said with reserve, as it is but roughly true, and not for all material surfaces.

The laws of skin friction may be applied with advantage to many practical questions in transportation. They show, for example, that every surface of constant major section has some length for which the resistance is a minimum, and beyond which it increases with the length. The symmetrical spindle outlined in one of the views illustrates this. Its resistance is a minimum when the length is about twelve calibers, or nearly seven times the major diameter. Beyond this length the friction exceeds the true head resistance. A still better form consists of a two-caliber bow, shown dotted in the figure, combined with a twelve-caliber stern, making the length about five times the major diameter. Similar results are found for posts having the form of a two-edged sword.

Take another illustration. It has been taught that the power needed to just support a thin plane gliding through air diminishes with the velocity, because the angle of flight decreases indefinitely with the speed, and the resistance was supposed to do the same. The fact is that after a certain moderate velocity the resistance of a

gliding plane, and still more so the propelling power, increase with the velocity. For instance, a thin foot-square gliding plane weighing one pound soars with the least expenditure of power at a speed of about 40 miles an hour, and at 80 miles an hour the power required is more than twice as much.

Again, the friction on a long railway train may equal or exceed the true head resistance, while on a short train or single car, the friction is comparatively inconsiderable. Now, though the head resistance may be very greatly reduced by sharpening the front and rear, the skin friction cannot be reduced appreciably by any treatment. Hence, it is apparent that the total air resistance of a long train or hull cannot be reduced very largely by any treatment, whereas the resistance of a single coach, like a street car or automobile, may be reduced several per cent by use of suitable prow and stern.

In conclusion, it may be said that both theory and experiment show that the atmospheric friction about equals the head resistance on symmetrical hulls of easiest shape, on double-edge sword shapes of least resistance, and on soaring planes gliding at the most economical angle of flight.

THE MORO FIRE MAKER.

BY C. H. CLAUDY.

The match has been said to be the greatest civilizer of the world, but it has not yet completed its work. There are still tribes of barbarous and semi-barbarous people who use nature's means for producing fire, either by friction with or without apparatus, or the contact of two substances which produce a spark, as flint and steel.

The Moros, of great interest to us on account of our experience with them in the East, use a method distinctive from other savage races, and of interest not only for its uniqueness, but as showing the effect of environment on invention.

This apparatus consists, as shown in the accompanying photograph, of a bamboo stick, a bit of china, and tinder. The cylindrical cases, which are also shown, are part of the device as it is used, one being a case for tobacco, and the other a case for the china and tinder. The whole, connected with cords, is worn at the belt. To use the apparatus, the native takes the bamboo firmly in his left hand, and in his right holds the bit of china by the finger and thumb, and on the thumb side pinches a bit of tinder. The edge of the china is then struck sharply down and along the bamboo, producing a bright and long spark, which catches in the tinder and ignites it. Very little practice is required to enable even a novice to light a fire by this means. Obviously, when the apparatus was first devised, no china was available, and doubtless some sharp stone took its place. Now, however, bits of broken china, such as are found in cheap eating houses, are regarded as best for the purpose, and universally used.

The thoughtful reader will at once draw an analogy between this means of fire making and the flint and steel of our own ancestors. In the eastern tropics, however, bamboo is the commonest of woods, and so was doubtless observed many times to make a bright spark when struck where flint, in contact with metal, was seen once. In consequence, after the first bright thinker had devised this way of using the spark, the method held its popularity and obtains to this day, although the flint and steel is so much simpler, easier, and more portable.

The philosophy of the device will at once be apparent. The sharp edge of the china scrapes off a bit of bamboo—not much, because the wood is hard and the outside has quite a glaze—but enough to be made incandescent by the friction of the stroke. The tinder catches this spark, and the desired flame is the result.

The photograph was made from the object in the possession of Mr. W. W. Dinwiddie, of Washington, D. C.

A Japanese observatory has been built at Chemulpo and was opened in March, 1905.

MOUNTING A MONSTER SEA ELEPHANT.

BY HAROLD J. SHEPSTONE.

A new and interesting attraction at the Berlin Zoological Garden is a mounted specimen of a monster sea elephant. It can claim the distinction of being the largest sea elephant that has ever been killed, while the mounting of the giant animal is undoubtedly a clever piece of taxidermic work.

It was found some eighteen months ago by whalers off the coast of the Falkland Islands. They promptly surrounded the monster, and subsequently slaughtered it—no easy task—and the hide with the raw skeleton was purchased at a high price by Mr. J. F. G. Umlauff, the proprietor of the famous Umlauff Museum in Hamburg.



MORO FIRE MAKER. BAMBOO TO BE STRUCK WITH CHINA AND TINDER.

He at once commenced the difficult task of mounting the giant sea mammal. It took him six months to complete the work, which cannot be regarded as an excessive amount of time. A laborious piece of work was the removing of the fatty matter from the skin, which was entirely permeated by blubber canals. Before the animal was finally dressed a model was made, and there being a distinct lack of pictorial representations of the sea elephant, the artist had very little material to guide him.

Some idea of the size of the monster may be gaged from the fact that from the tip of its tail to the tip of its tusk it has a total measurement of nearly 21 feet. Such an animal, when alive, would weigh 10,000 pounds, or nearly 4½ tons. The circumference of the body at its widest part is some 18 feet. The skull alone measures 2 feet 3 inches long and 1 foot 3 inches high. The sea elephant, or seal elephant, is in many ways an interesting creature. So far as size goes, he can give points to the walrus, but he is certainly not so ferocious looking. Except for the curious nose (whence his Greek name) he is just a big black seal fairly agile in the sea and clumsy ashore, like all his kind. He is about the bulk of a hippopotamus, although more hirsute and with a less extensive opening of the jaws. He holds among seals the unique position of being common to both hemispheres, although from the ardor with which he has been hunted, very few specimens exist now north of the equator. Just now, however, the sea elephant is enjoying a respite, and is consequently increasing in numbers rapidly, particularly in the southern seas. He forms practically the only population of many an otherwise lonely series of barren rocks in the Antarctic Ocean. His food consists chiefly, if not entirely, of cuttlefish. Formerly the animal was hunted by whalers upon all the islands of the Antarctic Ocean, notably Kerguelen's Land and the South Shetland, where they abounded in immense herds. The creatures were slaughtered for their hides and blubber.

The animal has derived the title elephant from the fact that it possesses a kind of trunk, or proboscis. This characteristic is only found, however, in the old males. It extends quite a foot beyond the angle of the mouth. In other respects, also, the males are distinguished from the females, more especially by their size. The female, on the average, attains only half of the length attained by the males, and only one-third the weight of the latter. Old males also lose the hair from the nether part of the neck, the skin thickening in this part and getting barky and cracked, deep intersected furrows dividing it into irregular patches. The tusks of the males reach a length of four to five inches, their external part being smooth and conical, while the part imbedded in the flesh is furrowed and slightly curved. The tusks of the males are solid; at the lower end only a slight cavity appears, while in the female they are shorter, and, moreover, almost hollow up to the point. Sailors and seal-hunters are fond of using these hollow teeth of the females for pipe-bowls, quills from the wings of pelicans supplying suitable stems for the pipes. The monster sea elephant seen in our picture has been mounted with penguins beside it. As already stated, it is the size of this sea mammal that has attracted attention. Even old, experienced whalers declare they have never met a larger specimen.



Skeleton of the Giant Sea Elephant.



From the tip of its tail to the tip of its tusk the specimen measures 21 feet.

THE GREAT SEA ELEPHANT. A REMARKABLE PIECE OF TAXIDERMIC WORK.

The first marine engineering in the modern sense was the adaptation of the steam engine as already in familiar use on shore to a modification of the centuries old method of mercantile propulsion, the oar. Some attempts were actually made to adapt the steam engine to a series of oars, which would have meant something like a mechanical trireme; but of course the trained mechanical sense soon saw that the collection of the oars in a revolving wheel was the correct solution. As oars had been used on both sides, so it was natural at first that the paddle wheels should be on both sides; a center wheel was also tried, but it is interesting to remark that practically about the same time that the sidewheels were used on the seaboard, the first marine engine was the shore engine modified to suit the circumstances, and thus on the seaboard the engine was designed and worked with what we now consider an exceedingly low pressure. On the western rivers, where the change has been made in the location of the wheel, there was also the additional change of dispensing with the condenser and using very much higher pressures. It was doubtless due to this fact—that the first non-condensing engines really carried a very high pressure—that the term "high pressure," in the early days meant non-condensing. The reason for the difference is of course very clear; the western rivers are very shallow and it was necessary to make the machinery as light as possible; on the seaboard and the rivers of that section there was deep water and the vessels could carry heavy machinery.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. **In every case it is necessary to give the number of the inquiry.**
MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.

Inquiry No. 7044.—For makers of engines for changing farm wagons and top buggies into traction vehicles.

For mining engines. J. S. Mundy, Newark, N. J.

Inquiry No. 7045.—For firms in the United States manufacturing apparatus for the dry distillation of wood, for producing alcohol, charcoal and other products.

"U. S." Metal Polish. Indianapolis. Samples free.

Inquiry No. 7046.—Wanted, manufacturers of gold brilliant sign letters stamped from copper plate, concave, finised inside with gold leaf, used on inside of glass or show windows.

2d-hand machinery. Walsh's Sons & Co., Newark, N.J.

Inquiry No. 7047.—Wanted, a meter for measuring gasoline gas.

Perforated Metals, Harrington & King Perforating Co., Chicago.

Inquiry No. 7048.—For manufacturers of a weight motor or blower to be used in connection with gasoline lighting system.

Handle & Spoke Mchy. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

Inquiry No. 7049.—For makers of small, wooden boxes.

Adding, multiplying and dividing machine, all in one. Felt & Tarrant Mfg. Co., Chicago.

Inquiry No. 7050.—For information in regard to the manufacture of paper bottles.

Sawmill machinery and outfits manufactured by the Lane Mfg. Co.. Box 13, Montpelier, Vt.

Inquiry No. 7051.—For makers of small, wooden articles turned out of wood.

Boyd's City Dispatch, city, furnish lists of manufacturers, jobbers, etc. Send for catalogue.

Inquiry No. 7052.—For dealers in magnetic sand ore containing gold.

I sell patents. To buy them on anything, or having one to sell, write Chas. A. Scott, 719 Mutual Life Building, Buffalo, N. Y.

Inquiry No. 7053.—For importers or manufacturers of the "La Luciole" French electric sign, illuminated.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Machine Company, Foot of East 138th Street, New York.

Inquiry No. 7054.—For makers of small commutators.

Gut strings for Lawn Tennis, Musical Instruments, and other purposes made by P. F. Turner, 46th Street and Packers Avenue, Chicago, Ill.

Inquiry No. 7055.—For dealers in pure oils and ingredients for use in making flavoring extracts.

WANTED. — Agency for South Africa of any new article or patent. Write with particulars. F. Smith, Cuthberts Bldgs., Woodstock, Cape Town, S. Africa.

Inquiry No. 7056.—Wanted, firms who underwrite stocks and bonds.

Sheet metal, any kind, cut, formed any shape. Die-making, wire forming, embossing, lettering, stamping, punching. Metal Stamping Co., Niagara Falls, N. Y.

Inquiry No. 7057.—For manufacturers of a certain Metropolitan lever handle loco. injector.

Manufacturers of patent articles, dies, metal stamping, screw machine work, hardware specialties, wood fiber machinery and tools. Quadriga Manufacturing Company, 18 South Canal Street, Chicago.

Inquiry No. 7058.—For the manufacturers of the collapsible foil metal tubes.

Space with power. heat, light and machinery, if desired, in a large New England manufacturing concern, having more room than is necessary for their business. Address Box No. 407, Providence, R. I.

Inquiry No. 7059.—For makers of small, gray iron castings.

Absolute privacy for inventors and experimenting A well-equipped private laboratory can be rented on moderate terms from the Electrical Testing Laboratories, 548 East 80th St., New York. Write to-day.

Inquiry No. 7060.—For parties engaged in cleaning dynamo belts, which have been oil soaked.

MOUNTAIN AND LAKE RESORTS.

Is the name of a beautifully illustrated publication of one hundred and twenty-eight pages just issued by the LACKAWANNA RAILROAD. The book contains a list of more than four hundred hotels and boarding houses among the various mountain and lake resorts reached by that road in New York, New Jersey and Pennsylvania. It suggests where to go, how to go, what it will cost and what can be seen and done when you get there. In addition there is a delightful love story entitled "A Paper Proposal," illustrated by well-known artists.

The book will be sent on receipt of ten cents in stamps addressed to T. W. LEE, General Passenger Agent, New York City.

Inquiry No. 7061.—For makers of turbine water wheels, from 2 to 10 h. p.

Inquiry No. 7062.—For a machine for making open ditches.

Inquiry No. 7063.—For a machine for preparing manila and sisal for binder twine.

Inquiry No. 7064.—For the makers of the patent clasp which is attached to suspenders.

Inquiry No. 7065.—For manufacturers of glass.

Inquiry No. 7066.—For makers of umbrella ribs and handles, and steel rods.

Inquiry No. 7067.—For manufacturers of furnishing fixtures for a toy shop.

Inquiry No. 7068.—For manufacturers of peroxide of iron. venetian red, corcus mortis, powdered pipe clay, chalk, oxalic acid.

Inquiry No. 7069.—Wanted, address of firms who underwrite stocks and bonds.

Inquiry No. 7070.—For the names of firms that make perfectly puncture-proof bicycle tires.

Inquiry No. 7071.—For manufacturers of machinery used in making bricks.

Inquiry No. 7072.—For manufacturers of plants for distilling turpentine, wood alcohol, creosote, etc., from rich pine stumps.

Inquiry No. 7073.—For manufacturers of the "Peerless Combination Sharpener."

Inquiry No. 7074.—For manufacturer of an article called "Flat Lap."

RECENTLY PATENTED INVENTIONS.

Electrical Devices.

TELEPHONE-SWITCHBOARD. — E. DARNELL, Carrollton, Mo. The inventor provides a compact switchboard in which the spring-jacks, plugs, and cords are all dispensed with with their incidental objections, and the movable parts to be adjusted are assembled within limits of an easily-reached and conveniently-managed switch, whereby the reaching movements are reduced in number, and so restricted in extent of reach as to greatly economize time, and whereby, also, enunciation between subscribers is rendered secret, so that operators can hear nothing after subscribers are put into communication with each other, and whereby disconnection between subscribers is placed under their own control.

Of General Interest.

ERASER.—H. H. HALL, Treichlers, Pa. The object had in view by the inventor is to combine in one device a sharpened blade and an erasive block of rubber, with the combination device affording advantages novel and useful over other erasers. One of the points of novelty resides in the shoulder and lug devices holding a blade at unfolded adjustment for effective use of its sharpened edge to a flange with its upturned edge, forming a guard for a sharpened edge of the blade when the latter is adjusted to folded position.

DAYLIGHT DEVELOPING APPARATUS.—A. O. GRAF and D. GRAF, New York, N. Y. In the present patent the invention has reference to photography; and the object is to provide a new and improved daylight developing apparatus arranged to allow convenient and quick developing, washing and fixing of exposed photographic plates in broad daylight without resorting to the use of a dark room.

PACKAGE-HANDLING DEVICE.—W. R. DENNIS, Denver, Col. In this instance the invention refers to improvements in devices for handling shelf goods of all descriptions usually sold in stores, the object being to provide a simple and novel device by means of which packages may be readily removed from the shelves or the like or placed thereon without danger of breaking or otherwise damaging the packages.

EASEL.—A. R. COBB, Shorthills, N. J. The present invention pertains particularly to improvements in artists' sketching-easels, the object had in view by the inventor being the provision of an easel of strong yet light construction that may be compactly folded when not in use or for convenience in carrying about.

TOY BUREAU.—A. D. CONVERSE, Winchendon, Mass. A purpose of this improvement is to provide a construction whereby the mirror and its frame may be placed for shipment or storage in a compartment at the back of the body of the bureau and held in a protected position, the top of the bureau body being at such time flush throughout, and to so locate the said compartment that when the mirror is stored therein it will not interfere with the action of the drawers.

DEVICE FOR HOLDING VALVES.—C. O. COLE, Bellingham, Wash. The invention relates to a device for holding valves and preventing their displacement when subjected to jarring or other motions. The principal object is to provide for holding valves as stated and at the same time permit them to be opened and closed without the necessity of loosening or tightening any of the parts or using separate tools of any kind.

Machines and Mechanical Devices.

MACHINE FOR CURLING HAT-BRIMS.—W. W. KEYS and D. A. FERGUSON, Yonkers, N. Y. The inventors provide an economic device for curling brims by steam and so construct a feed device for the curling-shackle that it retains the curl in the brim and may be released at any time from action on the brim, permitting the ready withdrawal of the brim from the shackle, and furthermore so construct the shackle that the steam will be equally distributed at the top and bottom of the curl in the brim which is produced by the shackle.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of the paper.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending July 11, 1905

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Abrading sheet, G. Gorton	794,496
Abrading surface, G. Gorton	794,495
Abrading surfaces, machine for making, G. Gorton	794,174
Adding and subtracting machine, A. F. Hansen	794,353
Advertising machine, automatic, Kingscote & Williams	794,232
Air brake connection joint, S. Feust	794,350
Air brake for railways, automatic, S. H. Heginbottom	794,222
Air moistening, C. A. Erbsloh	794,166
Aluminium compounds, making, L. R. Keogh	794,413
Ammunition box, H. W. Daly	794,663
Amusement device, W. T. Smythe	794,431
Amusement device, F. D. Knapp	794,511
Antirattler and thill pin lock, combined, L. J. Dillon	794,283
Audiphone, portable, E. W. Schneider	794,686
Automobile, M. J. Davin	794,666
Automobile body, convertible, H. F. Vogel	794,650
Automobile brake, J. Unser	794,382
Baking pan, J. S. Frey	794,292
Bale ties, machine for forming wire, E. A. Frantz	794,602
Baler frame, hay, J. H. Pitkin	794,379
Bar and joint bit, combination, C. W. Phillips	794,681
Bath apparatus, electrothermal, F. W. Weeks	794,208
Battery grid, storage, M. Heisser	794,501
Bearing box, conical, J. D. Alsup	794,154
Bed bottom support, C. L. Harrell	794,299
Bed, Davenport, R. Coopersmith	794,345
Bed, lounge, or the like, J. W. Petavel	794,378
Beds, elastic support for spring, F. A. Zielke	794,270
Beet topping machine, A. H. Kramer	794,514
Belt, conveyer, T. Robins, Jr	794,381
Belt, moisture carrying, G. Goldman	794,402
Bending roll, J. J. Boax	794,392
Binder, J. L. McMillan	794,536
Binder for papers, pamphlets, etc, B. F. Methven	794,529
Binder, loose leaf, E. T. Ford	794,290
Binder, loose leaf, R. W. Richards	794,682
Binder, temporary, R. F. Hight	794,223
Bit. See Bar and joint bit.	
Blackboard, D. W. Allen	794,653
Blank trimming machine, J. H. Haskins	794,221
Block signal system, automatic, J. Lanz	794,519
Blood and the product thereof, treating, J. Herbabny	794,623
Blowpipe, G. H. Brown	794,449
Boiler furnace, J. Siebel	794,556
Boot or shoe polishing machine, Oliver & Ohlgart	794,540
Bottle, S. J. Hyman	794,302
Bottle stopper, W. T. Abbott	794,478
Bottle, testing, C. Wagner	794,572
Bottle washer, C. Murbach	794,533
Box partition, G. Klenk	794,627
Box trimming machine self feed, J. E. Erickson	794,286
Bracelet or belt, automatically adjustable, J. J. Sommer	794,193
Brake beam, J. Green	794,404
Brooch pin fastening, P. A. Viersen	794,571
Brooder, G. H. Lee	794,520
Broom, C. T. Adair	794,332
Brush, fountain, W. L. Payn	794,638
Bucket, clam shell, G. H. Williams	794,330
Buckle, R. A. Brown	794,699
Building construction, T. O'Shea	794,246
Bung, N. A. Smith	794,258
Burglar alarm, F. C. & V. H. Kline	794,360
Button and loop clasp, M. M. Downer	794,455
Button, cuff or collar, M. F. Oebbecke	794,636
Cabinet, credit, S. L. Henry	794,405
Cabinet, kitchen, H. Clark	794,589
Cam finishing machine, G. Meyer	794,530
Cans to tipping or soldering machines, means for feeding, F. G. Dickerson	794,493
Car draft beam, railway, W. F. Richards	794,252
Car dumping mechanism, A. Becker	794,274
Car frame, railway, G. Gibbs, reissue	12,368
Car, gravity dumping, Boyle & Ustick	794,485
Car handling apparatus, L. F. Card	794,587
Car, metal, C. M. Carnahan	794,280
Car wheel and making same, W. B. Brayton	794,277
Carbureter, H. J. E. Hennebutte	794,502
Cart, log, R. J. Williams	794,576
Cartridge packet, E. G. Parkhurst	794,680
Carving machine, W. B. Hughes	794,182
Carving machine, automatic, M. De Tamble	794,282
Casing spear, E. B. Noble	794,308
Catalytic substance and making same, R. Knietsch	794,512
Cataract cylinder and dash pot, M. A. Replogle	794,312
Center gage, J. W. Fessler	794,170
Chair, P. Mackey	794,461
Check strap, E. Morrey	794,531
Chuck, Bergman & Elmer	794,582
Churn, W. B. Chalfant	794,490
Cigars, combined guiding and lighting device for, J. J. Shickluna	794,321
Circuit breaker, J. B. Laing	794,518
Clasp. See Button and loop clasp.	
Clock movement, H. S. Prentiss	794,380
Cloth drying machine, J. S. Johnston	794,228
Cloth, laying, A. O. Morse	794,307
Clover buncher, S. K. Dennis	794,164
Clutch mechanism, Ford-Smith & Coventry	794,291
Clutch mechanism, friction, M. Campbell	794,393
Coal cutting machine engine, J. G. Patterson	794,248
Coal piling apparatus, S. D. Warriner	794,574
Coin distributer, C. H. Hall	794,620
Coke oven, E. Coppee	794,662
Collar, L. M. Wilkinson	794,477
Collar and leash, dog, C. D. Stahlknecht	794,563
Collar, hameless horse, C. P. Randolph	794,311
Controlling mechanism, G. E. Turner	794,203
Conveyer, J. D. Buchanan	794,342
Conveyer, portable, G. E. Gannon	794,604
Cooker, steam, J. W. Bauman	794,335
Copper mattes, white metal, and blister copper in a single furnace, producing, R. Baggaley	794,272
Copy holder, S. N. McCloud	794,419
Corn popper, W. S. Coffman	794,344
Corn shocker, G. W. Hollister	794,300
Corn snapping and husking machine, E. M. Jetson	794,504
Corset, W. F. Brooks	794,698
Crane, overhead traveling, C. L. Taylor	794,200
Crate, V. E. Windell	794,439
Crate, bottle shipping, C. W. Smith	794,558
Crushing apparatus, M. Dickerson	794,703
Cultivator, W. Hull	794,408
Cultivator, cotton, H. Barditzky	794,696
Curd agitator, E. L. McKinnon	794,421
Curtain pole and curtain fastener, J. F. Koepp	794,414
Curtain stretcher pin, P. J. McGinnis	794,420
Cushion stuffing machine, O. Roop	794,467
Cuspidor, B. C. Crouse	794,347
Cutlery, table, C. K. Decherd	794,591
Cutting off machine, J. J. Boax	794,389
Damper, sheet metal, F. T. Myers	794,534
Dashboard, adjustable, H. Gottschalk	794,249
Decoy ducks or the like, manufacturing, Rimpler & Self	794,643
Disk, furrow opening, H. C. Ham	794,621
Display rack, L. Feldmann, Jr	794,456
Display stand and truck, combined, A. E. Beall	794,273
Display stand, revolving, D. H. Manwiller	794,418
Door catch, W. C. Kinard	794,626
Door construction, W. B. Gervais	794,295
Door hanger, H. Lobel	794,524
Door holder, A. J. Boland	794,657
Door mat, flexible metal, Karnaghan & Prescott	794,304
Door, screen, B. S. D. S. Martin	794,369
Door securer, M. Farrell	794,400
Door sill, air tight, C. J. Petit	794,424
Doubling and twisting machine, D. Schmutz	794,427
Draft deflector, J. Dellinger	794,163
Draft equalizer, A. M. Kindwall	794,231
Drainer, utensil, W. R. Green	794,617
Drawing table, T. King	794,359
Dressing comb, T. M. Noyes	794,244
Drill motor, electric, E. E. Drake	794,398
Driving mechanism, W. J. Bell	794,211
Drum, E. Boulanger	794,658
Drying apparatus, G. Stiff	794,564
Dust, water, and mud guard, combined, J. I. Maguire	794,239
Dye, new azo, A. Thauss	794,568
Dyeing, B. Richard	794,314
Dyeing machine, R. P. Smith	794,560
Ear muff, H. Smith	794,559
Elastic tired wheel, F. Keup	794,230
Electric circuit closer, M. Guett	794,220
Electric furnace, C. L. Saunders	794,255
Electric machine, dynamo, Balachowsky & Caire	794,210
Electric mator, B. G. Lamme	794,362
Electric motor and controlling means therefor, B. G. Lamme	794,363


"Star" Foot and Power Screw Cutting Automatic Cross Feed Lathes
FOR FINE, ACCURATE WORK
Send for Catalogue B.
SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N.Y., U. S. A.

ENGINE & FOOT LATHES. MACHINE SHOP OUTFITS. TOOLS AND SUPPLIES. CATALOGUE FREE. SEBASTIAN LATHE CO. 120 CULVERT ST. CINCINNATI, O.

GIANT STEAM SHOVELS

Toledo 125 Ohio, U.S.A. Vulcan Place
The Vulcan Iron Works Co.

Veeder Counters
to register reciprocating movements or revolutions. Cut full size.
Booklet Free
VEEDER MFG. CO.
Hartford, Conn.
Cyclometers, Odometers, Tachometers, Counters and Fine Castings.


Price $1.00

BEST FOR YOUR BOILER
A great saver of trouble, annoyance and money, of labor and anxiety is the
STANDARD STEAM TRAP.
It is a new invention that is simple and exceedingly durable. Working parts all on outside. Valves two-piece simple check operating automatically. No waste of steam or water. If you have a boiler investigate this trap.

E. HIPPARD, Manufacturer, YOUNGSTOWN, OHIO

PATENTS
Our Hand Book on Patents, Trade-Marks, etc., sent free. Patents procured through Munn & Co. receive free notice in the
SCIENTIFIC AMERICAN
MUNN & CO., 361 Broadway, N. Y.
BRANCH OFFICE: 625 F St., Washington, D.C.


The Right Kind of a Motor
on land or water. Salisbury Double Cylinder Motor 4¼ x 5. Water Jacket Cylinders and Head. Aluminum Crank Case, Self-Oiling, Nickel Steel Valves, Forged Steel Shaft. Salisbury Motors are Reliable. Prices moderate.
Send for Catalogue.
BUFFALO ENGINE CO., Mfrs.
272-274 Michigan St., Buffalo, N. Y.

THE MIDGET DYNAMO OR MOTOR

Price as shown $7.50
Without Hand Power $4.50
Price includes full instructions for the care of the machine and for performing 35 IMPORTANT EXPERIMENTS.
This machine has been on the market over ten years and has been gradually developed to its present state of perfection
ELBRIDGE ELECTRICAL MFG. CO.
Water St., ELBRIDGE, N. Y., U. S. A.


WOLVERINE
SELF STARTING AND REVERSING
Gasoline Marine Engines
3 to 18 horse power. Launches 18 to 75 ft. Write for catalogue.
WOLVERINE MOTOR WORKS
Grand Rapids, Mich., U. S. A.
Brooklyn office, 97 22d St.


The Wonder Gasoline Motors
Something New and Up-to-date
More power for less money than any other machine on the market. No valves, gears, etc., to get out of order. Jump Spark. Our 1½ H. P. marine outfit is a "WINNER." Solid or reversing propeller. Our prices will surprise you. Write to-day. Marine or stationary outfits to suit any requirements up to 5 H. P.
The R. M. Cornwell Co., 406 S. Salina St., SYRACUSE, N. Y.


THE "LEADER"
1½ H.P. Gasoline Auto-Marine Engine
Built like a watch. Beautifully Finished. Accurately Constructed. Light, Strong, Reliable and Noiseless in operation. Suitable for launches from 15 to 19 feet in length. Price complete, $75.00 net, no discount. Thoroughly guaranteed. Perfect Speed Control. Complete descriptive catalogue upon application.
MANUFACTURED BY
CLAUDE SINTZ,
92 S. Front St., Grand Rapids, Mich.

Igniter Dynamos
For all classes of
GAS ENGINES
for make and break or jump spark systems. Our latest type price $15. Write for circular of magnetos, etc.
THE CARLISLE & FINCH CO.
233 E. Clifton Ave.
Cincinnati, O.


Crescent Machinery
Quality and Price, both right
BAND SAWS. JOINTERS, SAW TABLES, BAND SAW BLADES
Catalogue tells the rest
CRESCENT MACHINE CO.
230 Main Street, Leetonia, O., U. S. A.

WILLIAMS' SHAVING STICK

The acme of luxury, convenience and economy.

Williams' Shaving Sticks, Shaving Tablets, Toilet Waters, Talcum Powder, Jersey Cream Toilet Soap.

Write for booklet "How to Shave"

THE J. B. WILLIAMS CO.
GLASTONBURY, CONN.

Medart Boat Building Materials



A system of supplying perfectly fitted boat parts, knocked down, enabling anyone handy with tools to build their own boat at one-half the boat factory's price. Freight low. Send stamp for catalog just issued.

FRED MEDART
8545 DeKalb Street
St. Louis, Mo.

SAFETY IN CASE OF FIRE

in all hotels, hospitals, asylums, theatres, churches, schools, factories and all public buildings, as well as private residences, is doubly assured when these structures are equipped with the

COVERT FIRE ESCAPE



Each room and window is provided with a safe and permanent means of egress, obviating the rushing through smoky or burning halls and corridors and consequent dangers to life and limb. Any number of people can escape easily and quickly by the new method. Best and most economical fire escape system ever devised. For circulars and full particulars, address

COVERT FIRE ESCAPE CO., - TROY, N. Y.

Road Freighting Traction Engines



Over 200 in use on Pacific Coast alone. Siberia, Spain, India, Central America, Sandwich Islands have them.

Engines 110 Horse-power. Wood, Coal, or Oil burning. Hauls 50 tons, takes grades 5 to 25 per cent. Capacity each car 16 tons.

THE BEST MFG. COMPANY
San Leandro, California

Cable Address, DANBEST. Codes, Western Union and McNiel. *Write for our New Catalogue No. 18.*

HOW TO MAKE AN ELECTRICAL

Furnace for Amateur's Use.—The utilization of 110 volt electric circuits for small furnace work. By N. Monroe Hopkins. This valuable article is accompanied by detailed working drawings on a large scale, and the furnace can be made by any amateur who is versed in the use of tools. This article is contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1182. Price 10 cents. For sale by MUNN & Co., 361 Broadway, New York City, or by any bookseller or newsdealer.



If you have an **Apple Automatic Sparker** your batteries will always give a strong, hot, steady spark. Owners of launches, automobiles or gas engines should write today and learn of this perfect storage battery charger.

The Dayton Electrical Mfg. Co.
98 Beaver Bldg. Dayton, Ohio.

American Homes and Gardens

A MONTHLY Magazine devoted to the illustration of homes, their interior decorations and surroundings. Illustrations of the way gardens may be beautified and laid out; the most suitable flowers to be planted in different parts of the garden, etc. Articles are published on room decoration and furnishings, showing how the furniture may be arranged to produce the best effects. Plans are published of most of the residences shown. A valuable and instructive magazine for future home builders to possess, as well as for up-to-date architects. Issued monthly. 72 pages each number. Price 25 cents per copy; $3.00 the year.

MUNN & CO., Publishers
361 Broadway, New York

Electric motor controller, F. Wright	794,442
Electric switch, W. E. Dow	794,218
Electrical controller, R. P. Jackson	794,358
Electrical meters, construction of, O. T. Blathy	794,656
Electrode, medical battery, K. L. V. Curry	794,161
Elevator, M. Fullenlove	794,293
Elevator gate, automatic, J. H. Morris	794,306
Elevator winding machine, M. Turnbull	794,264
Elliptic spring, J. J. Flanagan	794,289
Embroidering machine, R. Zahn	794,331
End gate, Holt & Hudson	794,355
End gate, wagon bed, W. F. Wagner	794,328
Engines. See Internal combustion engine.	
Engine starting means, gas, W. J. Bell	794,275
Engines, means for balancing compound, E. P. Clapp	794,281
Engraved plates when printing therefrom, wiper for cleaning the surfaces of, F. E. Blaisdell	794,213
Envelop, S. J. Mathews	794,527
Excavating apparatus, W. J. Newman	794,243
Excavating machine, A. N. Cross	794,346
Excavating machine, C. C. Jacobs	794,410
Excavating machine, L. W. & H. W. Hoadley	794,624
Explosive composition, H. Boyd	794,583
Fare register, W. G. Kirchhoff....794,508,	794,509
Farm implement, W. Daly	794,396
Fastening, J. Bagnall	794,695
Feet, device for relief of club or flat, W. M. Scholl	794,256
Fence tie, F. W. Reed	794,250
Fertilizer distributer, C. Johnson	794,505
Fiber material, apparatus for feeding strips of short, R. Kron	794,516
File, letter or bill, T. P. Loblaw	794,237
File, paper, J. N. Talbott	794,648
Filter, drum, E. Fullner	794,173
Filtering apparatus, J. S. Milne	794,631
Fire apparatus, B. B. Briggs.....794,278,	794,486
Fire escape apparatus, self saving, F. Stabe	794,562
Fireproof ceiling and floor, J. Weber	794,438
Fireproof structure, F. L. Saino	794,316
Fish catching apparatus, M. Ward	794,573
Fish hook, V. Gebhardt	794,352
Flagstaff, P. H. & F. F. Downes	794,668
Flat iron heater, A. V. Maniachi	794,417
Flax breaking machine, G. H. Ellis	794,284
Floor grinding and polishing machine, G. Lyon	794,305
Floor or wall covering, wood, W. Gutwasser	794,672
Flue cutter and expander, S. W. Blevins	794,337
Fluid gage, M. Martin, 794,675, 794,676, 794,678,	794,679
Fluid operated gage, M. Martin	794,677
Fly exterminator, Park & Jones	794,637
Food, article of, A. A. Faust	794,287
Fuel burner, T. W. Phillips, Jr	794,545
Fuel from seaweeds, manufacturing, D. M. Balch	794,481
Fungicide and making same, F. J. Smith	794,644
Furnace charging apparatus, R. Baggaley	794,386
Furnace charging device, J. J. Boax	794,391
Furnace grate, A. Wilkinson	794,575
Fusee, W. E. Matthew	794,371
Gage or similar tool, C. J. W. Hayes	794,500
Garbage crematory, portable, I. D. Smead	794,471
Garment fastener, M. E. Kintz	794,183
Garment holder, F. J. Hamilton	794,176
Garment supporter, F. Ferguson, reissue	12,372
Gas burner, A. H. Humphrey	794,225
Gas burner for singeing machines, H. H. Skevington, et al	794,429
Gas generating apparatus, L. Guenot, Fils	794,498
Gas generator, acetylene, T. Lindenberg	794,236
Gas purifying apparatus, centrifugal, E. Theisen	794,201
Gate, H. H. Gorton	794,403
Gear, speed changing, T. W. Jenny	794,227
Gear, speed changing and transmission, I. H. Pleukharp, reissue	12,369
Gearing, transmission, E. Hill	794,224
Glass fastener, plate, W. R. Bickford	794,447
Glass machine, L. P. Holston	794,179
Governor, F. G. Hobart	794,178
Grain drill, O. Schutt	794,191
Grass cutter, F. A. Nelson	794,422
Grinding machine, L. F. Brening	794,159
Grinding mechanism, J. Nazel	794,375
Gun sighting apparatus, E. Ternstrom	794,649
Gyroscope, H. Anschutz-Kaempfe	794,654
Hame fastener, E. G. Bennett	794,336
Hams, bacon, or the like, machine for branding and polishing, R. Wirth	794,440
Harness, wire ribbed, W. Dann	794,453
Harrow and sulky, combined, D. H. Brown	794,339
Harvester, corn, W. T. Poff	794,547
Harvester, cotton, J. S. Watson	794,265
Harvester guard, J. Lutin	794,238
Harvesting machine thill attachment, J. W. Latimer	794,235
Hay and stock rack, C. L. Clark	794,491
Heat control, automatic electric, J. I. Ayer	794,580
Heater. See Flat iron heater.	
Heating apparatus, M. Rapp	794,550
Heating system, hot water, H. A. Bolze	794,157
Hedge trimmer, E. J. Nolting	794,538
Hinge, Davis & Brown	794,454
Hoist and carrier, J. F. & G. J. Kropp	794,517
Hose coupling, J. D. O'Brien	794,539
Hose reel bracket, G. Erxleben	794,399
Hub and bearing, wheel, H. M. Butler	794,489
Hydrometer, Beck & Smith	794,697
Incubator, G. H. Lee	794,521
Inhaler, A. H. Ramey	794,641
Ink well, F. C. Luethy	794,366
Insulating block for electric light canopies, I. J. Parker	794,309
Insulator bracket for telephone poles, etc., K. G. Springen	794,645
Internal combustion engine, J. W. Seal	794,192
Internal combustion motor, C. C. Riotte	794,683
Ironing machine, H. A. Utley	794,383
Joint, D. D. Palmer	794,247
Journal box, T. H. Symington	794,259
Journal box dust guard, railway, T. H. Symington 794,260,	794,261
Journal box lid, J. S. Patten	794,542
Key opening can, C. Jovignot	794,229
Kneading apparatus, dough, J. Nazel	794,376
Knitting machine pattern mechanism, F. B. Wildman	794,474
Knitting machine pattern mechanism, Wildman & Loomis	794,475
Knitting machines, thread changing mechanism for circular, E. A. Hirner	794,407
Lamp, electric arc, M. A. Stogsdill	794,565
Lamp, electric display, H. J. Gille	794,296
Lamp, flash, G. H. Saunders	794,189
Lamp socket, incandescent electric, L. C. Gollatz	794,458
Lamps, mantle holder for incandescent, T. Brabson	794,158
Lamps, manufacturing incandescent electric, H. Casassa	794,588
Lantern, W. S. Hamm.....794,297,	794,298
Ledger sheet and monthly statement filing holder, A. Inglis-Donnell	794,303
Level, A. P. Hall	794,175
Level and plumb, E. R. Brodton	794,659
Lifting jack, pneumatic, F. E. Ten Eyck	794,262
Line holder, L. B. Tompkins	794,570
Linotype machine, R. J. Foster	794,670
Locomotive boiler, J. F. Sweeney	794,566
Loom attendance, apparatus for facilitating, F. G. Cobb	794,701
Loom filling tension device, A. L. Scarboro	794,685
Loom shuttle, C. B. Webster, reissue	12,371
Loom weft replenishing mechanism, F. O'Donnel	794,377
Loom weft replenishing mechanism, E. D. Thayer, reissue	12,370
Looms and the appliances used therein, production of heddles for use in, T. E. Dean	794,590
Lubricator, W. B. Featherstone	794,167
Magnetic separator, electrostatic, H. M. Sutton, et al	794,647
Mail bag delivery device, P. J. A. Schnoor	794,554
Malt house and malting apparatus, W. P. Rice	794,313
Mandrel or arbor, expanding, C. J. Jones	794,411
Mandrel swing for bending dies, J. J. Boax	794,390
Mantles, heating to incandescense refractory, J. Herczeg	794,406
Manure spreader, L. Kniffen	794,513
Marker, personal wear, J. B. Spencer	794,561
Match safe, B. F. Fulgham	794,603
Measuring device, tailor's, G. B. Kaiser	794,506
Measuring instrument, electrical, F. Conrad	794,395
Measuring, protecting, and display means for fabrics, A. E. Standen	794,689
Meat products, curing, W. Eppinger	794,285

Build Your Own Boat
By the Brooks System.

You can build your own Launch—Sailboat—Rowboat or Canoe—in your leisure time—evenings—and the work will be a source of profit and pleasure. It's easy when we show you how.

$12 covers the cost of a $50 boat. Cheaper boats cost less in proportion. Write us—we'll tell you how.

The Brooks System consists of exact size **Printed Patterns** of every piece, with **Detailed Instructions,** a complete set of **Working Illustrations,** showing each step of the work, an itemized bill of **Material** required and how to secure it.

Our system is so plain you cannot fail. A full sized pattern of each piece with instructions that not only TELL, but SHOW you, by illustrations, every detail.

Over six thousand amateurs successfully built boats by the Brooks System last year. Fifty per cent. of them have built their second boat. Many have established themselves in the boat manufacturing business.

Patterns of all kinds and sizes from 12 to 55 ft. Prices from $2.50 up—Catalogue and particulars FREE. For 25c, 100 page catalogue containing valuable information for the amateur yachtsman, showing several working illustrations of each boat, and a full set for one boat. Full line of knock-down and completed boats. When so ordered—Patterns are expressed, charges prepaid, C. O. D. to allow examination.

BROOKS BOAT MANUFACTURING CO.
Originators of the Pattern System of Boat Building
407 Ship Street, Bay City, Mich., U. S. A.

Clean House With Air

Over 55 companies operating Thurman Patents in America, and as many more in Canada, England, and Europe.

FREE CATALOGUE.

General Compressed Air House Cleaning Co.
ST. LOUIS, U. S. A.

Manufacturers of the Celebrated Thurman direct-connected Gasolene Driven Air Compressors for Mines, Pneumatic Tools, Etc.

THE HARRINGTON & KING PERFORATING CO.
PERFORATED METALS OF EVERY DESCRIPTION FOR ALL USES.
SCREENS OF ALL KINDS.
225 NORTH UNION ST. CHICAGO, ILL.

The Only System

That **MOISTENS DRIES COOLS WARMS** **AIR**

Removes Dust and Ventilates.

Its versatility is proof of its correctness.

100 per cent. of our installations are successful.

Regenerated Cold Air Co.
88 Broad Street, BOSTON, MASS.

THE YANKEE SILENT MUFFLER
(PAT'D)



Excels all mufflers because the discs expand according to the size of the explosion. A vacuum is created between the exhaust valves and the muffler, and back-pressure is overcome. 10 per cent. more power guaranteed. Radiation so great that the muffler keeps cool. Made to fit all makes of cars. Send for catalog and price.

D. B. SMITH & CO., Utica, N. Y., U. S. A.

"ANATOMY OF THE AUTOMOBILE"
By DR. DYKE

Contains full descriptions, detailed mechanical drawings and full operating instructions for all standard American automobiles and several foreign cars. DIAGRAMS OF ELECTRICAL CONNECTIONS. Full descriptions and drawings of successful AIRSHIPS. Three books in one. Over 700 pages and 300 illustrations. Invaluable to the auto owner, agent, repairman and intending purchaser. **Price, postpaid, $2.50.** Synopsis sent on request. Get our catalogue of auto supplies.

A. L. Dyke Auto Supply Co., Olive and Walton Sts., St. Louis
ROBT. F. BRITTON, Pres. and Mgr. ROY F. BRITTON, Sec. and Treas.

A LOOSE LEAF BOOK
For Vest Pocket, Coat Pocket and Desk



Used by Business Men, Professional Men, Salesmen, Engineers, Draughtsmen—in fact every man should use the "Unimatic" Book for memoranda, prices, costs and records of all kinds. Better than any card index. The **"Unimatic"** bound in full genuine black leather, flexible; is perfectly flat opening, and sheets may be instantly inserted or removed from any part. Twenty-eight sizes carried in stock. Five rulings, with or without index. Write for complete description price list and sample sheets.

SIEBER & TRUSSELL MFG. COMPANY
4002 Laclede Ave., St. Louis



SAVE for your Own and your Family's Future

You may be surprised to know how profitably you can invest even an average of $2.00 per week in Endowment Life Insurance in

The Prudential

Cash amount payable to you (if living) in 10, 15 or 20 years with Dividends (according to plan selected).

If the Insured dies before the end of the Endowment Period, the full amount of the policy is paid to the beneficiary.

We desire to correspond with you on the subject and furnish full information as to Rates, Benefits and Privileges.

Send Coupon today

Without committing myself to any action, I shall be glad to receive free particulars and rates of Endowment Policies.

Amount.....
Name.....
Address.....
Occupation.....

To the Prudential Insurance Co. of America
Incorporated as a Stock Co. by the State of New Jersey.
JOHN F. DRYDEN, President **Home Office: Dept. 121 NEWARK, N. J.**

Hydrozone

Cures

Sore Throat

A Harmless Antiseptic.

Endorsed by the medical profession. Send ten cents to pay postage on **free trial bottle.** Sold by Leading Druggists. Not genuine unless label bears my signature:

Prof. Charles Marchand

Dept. U, **63 Prince St., N. Y.**

Write for free booklet on Rational Treatment of Disease.

Do You Know

that the appearance of your product is one-half of the selling point?

If you use enamel, why not the best? That means

BRAZILO

The pigments selected for **Brazilo Enamels** are of the finest, and after being bolted through silk of about 10,000 meshes to the square inch are ground in Hard Finish Brazilo, which makes an enamel especially adapted for ***ONE COAT WORK*** on wood and metals of all kinds. This process of manufacture is protected by us.

Brazilo enamels dry from the bottom up, producing a hard, smooth finish which will not chip or peel.

ALL COLORS. WRITE FOR COLOR CARD.

THAYER BROS. CO., WARREN, O.,

Manufacturers of the celebrated "GOLD LEAF LACQUER"



THE HANNA MFG. CO.

Engineering Instruments

382 River Street, Troy, N. Y.

Illustrated Catalogue on Application

NOW READY

Bound Volume

OF THE

SCIENTIFIC AMERICAN BUILDING MONTHLY

VOLUME XXXIX

January to June, 1905

277 Illustrations 6 Covers in Tint
132 Pages

PRICE OF SEMI-ANNUAL VOLUME $2.00, POSTAGE PAID

SPECIAL FEATURES

Notable American Houses. By Barr Ferree.

Mrs. A. Cass Canfield's House, Roslyn, L. I., N. Y.
The House of Ogden Mills, Esq., Staatsburg, N. Y.
"Bellefontaine," the Estate of Giraud Foster, Esq., Lenox, Mass.
The House of Lloyd Bryce, Esq., Roslyn, L. I., N.Y.
"Martin Hall," the House of James E. Martin, Esq., Great Neck, L. I., N. Y.
"Talbot House," the Estate of Talbot J. Taylor, Esq., Cedarhurst, L. I., N. Y.

Helps to Home Building. What the House Builder should know. Difficulties to Overcome. The Plan. The Structure. Designing the House. The Rooms and Their Uses.

Departments. Roads. Landscape Architecture. Ventilation. New Building Patents. Publishers' Department. The Automobile. The Plumber. Exhibitions. Correspondence. Fire Protection. Civic Betterment. Unknown Buildings. The House. Monthly Comment. The Household. The Garden. Fifty Suggestions for the House. The House Interior. New Books. Sanitation.

The Building Monthly aims to help its readers to better building. The illustrations reproduce homes and other structures of the highest grade and of varying costs. It seeks to interest the architect, the house owner, the real estate promoter, the home maker, and the builder. It stands for the good and the true and the beautiful in the art. Its series on "Notable American Houses" describes and illustrates with great wealth of illustrations the most important of the best large houses recently built in the United States and brings its readers in immediate touch with the most important work of the leading architects of the day. Its descriptions of houses are brief but compact with information. Its departments constitute a "review of reviews," summary of current comment, suggestion and help in all matters relating to the construction of the home, its decoration, equipment, and use.

Volume XXXIX, January to June, 1905, price $2.00. Six covers in tint and three hundred and eight illustrations. A rich conspectus of interesting notable houses. Many fine estates are treated with ample fullness. The discussions of current architectural themes are of permanent value and of unusual interest.

FOR SALE BY

MUNN & COMPANY

No. 361 Broadway, New York City

AND ALL NEWSDEALERS

Mechanical motor, E. Putnam	794,549
Metal, expanded, J. Kahn	794,412
Metalliferous materials, purifying and modulizing, T. C. King	794,673
Metallurgical furnace, G. H. Benjamin	794,212
Mine ventilation, F. C. Weber	794,384
Molding machine, C. Herman	794,177
Mosaic work, H. A. Litz	794,523
Muffler, P. J. & G. J. Ihrig	794,226
Music holder, J. Hoffman	794,503
Musical instrument, P. Wuest, Jr	794,443
Musical instrument valve, pneumatic, F. de Kleist	794,674
Nail trimmer, H. La Casse	794,234
Nitrocellulose or similar substances, making compounds of, D. Bachrach	794,581
Nozzle, locomotive exhaust, J. K. Booth	794,214
Nut and pipe wrench, K. Peterson	794,249
Nut lock, D. A. Frick	794,172
Nut lock, H. E. Clapper	794,450
Oils, chemically modifying, E. Meusel	794,373
Ordnance and firearm, Young & Sheriff	794,652
Ore and gathering gold or precious metal diffused in the employed mercury, treating, G. M. Rice	794,552
Ore concentrator, H. Scovell, et al	794,555
Packing hydraulic, G. J. Bryen	794,341
Pail, milking, P. H. Sanger	794,254
Pan. See Baking pan.	
Paper cutting machines, counting machine for, M. McCallum	794,374
Paper feeding device, M. B. Ferguson	794,401
Paper hanger's pedestal, J. R. Brown	794,585
Papers, pads, tickets, cards, etc., holder for, A. A. Low	794,415
Peach splitting and pitting machine, S. J. Dunkley	794,598
Penholder or pencil finger guard, W. A. Whitehouse	794,329
Phonograph record cylinder, E. N. Dickerson	794,592
Photograph machines, loading device for automatic, G. N. Pifer	794,639
Pianissimo device, W. & C. Kreter	794,515
Piano action bracket, J. Davenport	794,665
Piano frame, H. Hornbeck	794,356
Piano or organ pedal lever mounting, L. Lemieux	794,522
Piano plate, J. Davenport	794,664
Piling, metal sheet, H. Wittekind	794,268
Pillow sham holder, A. Guth	794,619
Pin, C. F. Markham	794,368
Pipe clean out fitting, soil, Dozier & Stallings	794,165
Pipe coupling, swivel, A. J. Hageman	794,499
Pipe wrench, H. B. Best	794,482
Plane, G. Dechant	794,667
Planers, etc., truing guide surfaces of, S. McMillen	794,537
Plow, E. R. Lesher	794,364
Plow disk bearing, W. G. Danielsen	794,452
Poison vault, W. S. Small	794,323
Pompadour comb, H. A. Austin	794,479
Portable house, W. M. Ducker	794,595
Pot lid holder or wall pocket wire, G. P. Bosbrink	794,436
Potato cutter, H. H. Tomlinson	794,327
Press, M. Sklovsky	794,430
Printer's quoin, L. L. Rogers	794,188
Printing mechanism, adding machine, C. Wales	794,205
Printing, photomechanical, H. L. Reckard	794,551
Printing press, L. A. Brod	794,487
Printing press web supplying device, H. A. W. Wood	794,578
Projectile, J. Shearman	794,468
Propellor, vessel, J. Saunders, Jr	794,317
Protecting box or casing, H. W. Clark	794,661
Protractor, W. L. Thomas	794,569
Pulp from sawdust, mechanical preparation of wood, H. C. Pfeifer	794,187
Pump, W. J. Pennock	794,186
Pump valve, B. C. Woodford	794,209
Pump, variable stroke, G. W. Sinclair	794,257
Pumps, wearing ring for centrifugal, E. Meden	794,184, 794,185
Pumping jack, G. Pitcher	794,546
Punching device, sheet metal, J. Wilderman	794,476
Radiator, corrugated, W. E. Roys	794,315
Rail joint, J. Hubbard	794,180
Rail joint, T. & L. Slingland	794,322
Rail joint and bond, combined, B. Wolhaupter	794,441
Rail, third, E. R. Brodlton	794,660
Railway signaling, electric circuits for, H. W. Spang	794,194 to 794,196
Railway switch, automatic electric, W. D. Woolley	794,269
Railway tie and rail fastening, Brown & Lauman	794,279
Railway traffic controlling apparatus, T. H. Patenall	794,423
Rand pressing die, J. & J. A. Barbour	794,445
Razor holder and sharpener, B. A. Robeson	794,253
Refrigerator, G. A. Masters	794,462
Refrigerator, A. H. Merrill	794,630
Regenerator, water sealed, G. Walzel	794,207
Regulator. See Voltage regulator.	
Rein guard, T. E. Schumpert	794,319
Restraining device, J. Gaiter	794,457
Reversing and speed changing mechanism, R. Symmonds, Jr.	794,567
Rollers, making, S. Crump	794,492
Rolling disk wheels or similar articles, apparatus for, A. de Fontaine	794,171
Roofing material, R. R. Walker	794,206
Rule and square, combined, J. Irving, Jr	794,409
Sample case box or tray, W. H. Clements	794,451
Sand blast apparatus, W. R. King	794,507
Sanitary shield, H. E. Hudson	794,181
Sash holder, J. B. P. Michaud	794,241
Sash lock, ventilating, W. A. Nichols	794,463
Saw swage, J. H. Brown	794,340
Screen, F. C. Wright	794,385
Self lubricating wheel, S. G. Porter	794,640
Separator, D. C. Ruth	794,425
Sewed signature, D. G. Smyth	794,688
Sewing machine attachment, J. T. Bearden	794,655
Sewing machine binder, H. P. Steward	794,690
Shaft support, H. Morton	794,532
Sharpening and repairing machine, drill, J. J. Brossoit	794,584
Sheet metal, means for removing superfluous metallic coating from, Fellows & Hopkins	794,704, 794,705
Sheet metal, removing superfluous metallic coating from, Fellows & Hopkins,	794,168, 794,169
Shoe, J. McBrearty	794,535
Show case, C. A. Sullivan	794,646
Signaling and electropneumatic train control system, electric, J. A. Whyte	794,266
Signaling apparatus, G. C. Graham	794,616
Signals, electric apparatus for producing sound, C. H. O'Brien	794,245
Sink cover, A. Beauchemin	794,388
Sleeve protector, H. Gardner	794,294
Smoke preventing means, H. H. Hughes	794,357
Socket joint, W. Burke	794,488
Soldering end seams of cans, machine for, G. H. Stewart	794,692
Soldering side seams of cans, machine for, G. H. Stewart	794,691
Sound record locating device, N. C. Durand	794,599
Sound reproducer, T. H. Macdonald	794,416
Speed mechanism, variable, J. Parker	794,464
Spindle bobbin clutch, rotatable, W. E. Allen	794,694
Spindle bobbin driving means, rotatable, F. H. Thompson	794,693
Spinning bobbins, apparatus for making, Peck & Hird	794,543
Spinning or twisting apparatus, ring, W. T. Carroll	794,700
Spring construction, W. Ott	794,541
Spring wheel, C. M. Tipton	794,202
Stairways, grated step for traveling, D. M. & T. R. Quay	794,465
Station indicator, J. B. & J. L. Henderson	794,622
Stave jointer, O. A. Sowers	794,432
Steel trap, D. Rupp	794,684
Stereotype plate casting and finishing machine, B. F. Curtis	794,162
Stone building block, artificial, H. Kline	794,510
Stool, store, O. E. Bolling	794,276
Storage battery, electric, Meister & Junker	794,240
Store service apparatus, J. J. Crist	794,216
Stovepipe thimble, R. T. Holton	794,301
Strainer and separator, J. G. Anson	794,271
Strainer, starch or jelly, L. A. Mangold	794,525
Stringer instrument with vibrating resonance board suspended within the resonance box, C. F. J. Appelberg	794,333
Suppositorial bougie, S. L. Kistler	794,233

Model K, $3,000



Victoria or Folding Extension Top, $200 extra

A Car of Profit and Pleasure

In selecting a car it isn't the price that should be given first consideration, but what you get for what you pay should determine if you've made a profitable purchase.

It's also necessary to choose a car that's so good that you'll always have pleasure when using it.

Such a car is the

HAYNES

Catalogue on request

THE HAYNES-Apperson CO.
Kokomo, Ind.
Member A.L.A.M.

New York **Chicago**

Save Time and Money

Progressive business men use

BATES
Hand Numbering Machine

It prints numbers consecutively, duplicates or repeats—changed instantly by turning pointer. To learn how it will save for you, send for Booklet 48 now.

BATES MFG. CO., 31 Union Sq., New York
CHICAGO—304 Wabash Avenue
Factory, Orange, N. J.

SAVE FIRE LOSS

PROTECT YOUR HOMES AND PROPERTY.

Badger's Fire Extinguisher will put out any kind of a fire at the start.

So simple a child can use it.

Write for information.

BADGER FIRE EXTINGUISHER CO.
30 Portland St., Boston, Mass.



PAT. AUG. 03

LUXURY IN TRAVEL

"THEY NEVER DISAPPOINT"

GRAHAM SUPPLEMENTARY SPIRAL SPRINGS FOR HARD RIDING AUTOMOBILES

CAN BE ATTACHED TO ANY CAR.
BOOKLET FREE. **THE GRAHAM CO.**
8 PARK PLACE, NEW YORK CITY, U.S.A.

TRAVEL PRIVILEGES

Some very interesting privileges are presented for the enjoyment of travelers over the LAKE SHORE & MICHIGAN SOUTHERN RY. this summer, as follows:

Stop-over at Niagara Falls for a period not to exceed ten days,

Stop-over at Westfield, N. Y., for a visit to Lake Chautauqua.

Stop-over at Sandusky for a side trip visit to Put-in-Bay and Cedar Point.

Option of traveling by boat or rail, either way, between Cleveland and Buffalo. Does not apply on tickets sold locally between those cities.

Option of traveling between Albany and New York City, either way, on Hudson River (day or night) boats, or rail on New York Central.

These matters are explained in folder, "Travel Privileges," sent free on request.

As a route for vacation journeys the LAKE SHORE is unexcelled, reaching practically, by its through trains or direct connections, all the leading summer places east and west.

The widespread popularity of the LAKE SHORE is a matter of much comment; the explanation is simple—it maintains in the highest degree of perfection everything that enters into the successful operation of its train service, so that its patrons travel safely, comfortably and promptly.

For any desired particulars address

C. F. DALY, Passenger Traffic Manager, CHICAGO, ILL.
A. J. SMITH, General Passenger Agent, CLEVELAND, OHIO.

"THE MIDNIGHT SUN" SOLAR MOTOR LAMPS



If it's a "good enough" car, maybe a "good enough" lamp is good enough. Otherwise—

Why, a SOLAR!

Illustrated book with prices for the asking

BADGER BRASS MFG. CO.
Kenosha, Wis.
New York Office, 11 Warren St.



A MONEY MAKER

Hollow Concrete Building Blocks. Best, Fastest, Simplest, Cheapest Machine. Fully guaranteed.

THE PETTYJOHN CO.
615 N. 6th Street, Terre Haute, Ind.

THE MIETZ & WEISS



Sizes from 1 to 60 H. P.

Send for Catalogue.

OIL ENGINES

Operated by Kerosene Oil, Fuel Oil, Distillate. Safest, Simplest, Most Economical and Most Reliable Power on the market.

Highest award for Direct Coupled Oil Engines and Generator, Paris Exposition, 1900. Gold Medals, Pan American Exposition, 1901, Charleston Exposition, 1902. Gold Medal and Special Diploma, Louisiana Purchase Exposition, St. Louis, Mo., 1904.

AUGUST MIETZ
128-138 Mott St., New York, U.S.A.
Catalogue Dept. **24.**

OSGOOD STANDARD SCALES

For Factory, Store and Farm

Send for Catalogue S.

Osgood Scale Co., Binghamton, N. Y.

Run No Risks With An Auto!

Test your batteries every time before starting out, it may save towing expenses.

An accurate volt meter up to ten volts and ammeter up to 25 amperes. Either one delivered prepaid on receipt of $3.50: the cheapest price on record.

All Automobile supplies at the same low figures.

THE MOTOR CAR EQUIPMENT CO.,
43 Cortlandt Street, N. Y.

ELECTRO MOTOR, SIMPLE, HOW TO make.—By G. M. Hopkins. Description of a small electric motor devised and constructed with a view to assisting amateurs to make a motor which might be driven with advantage by a current derived from a battery, and which would have sufficient power to operate a foot lathe or any machine requiring not over one man power. With 11 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **641.** Price 10 cents. To be had at this office and from all newsdealers.



SPRINGFIELD ABRASIVE POLISHING WHEELS AND BLOCKS.

Used for polishing machinery, cutlery, and edge tools of all kinds and for removing rust spots from highly polished metal. Makes a very smooth surface without marring. Containing rubber which gives it the resilient effect. Made with either Emery or Carborundum in different grades. Write for price list and special trade discounts.

The Springfield Tire and Rubber Co.,
SPRINGFIELD, OHIO, U. S. A.

PAN-TOG A GENTLEMAN'S DRESSING CHAIR

which presses and creases your trousers while you sleep. Provides an improved hanger for coat and vest, a handy place for slippers or shoes. This chair will **positively** prevent baggy knees by 500 lbs. pressure instantly applied. Your clothing will appear as **fresh every morning** as if just from the tailor's. Saves its cost in 6 months and will last a lifetime. Indispensable in a gentleman's apartment. Price within reach of all. Write today for illustrated descriptive folder and price.



CENTRAL MANTEL CO. 1212 Olive St., St. Louis, Mo.



Manufacturers should investigate the

B. F. BARNES MACHINE TOOLS

before placing orders. The Tool here illustrated is our 20-inch Drill, and we have many other sizes to make a very complete line, including Multiple Spindle Drills. If interested in the latest Tools for reducing costs of production, let us tell you what we have. Ask for Catalog S.

B. F. BARNES CO. - Rockford, Ill.
European Branch
149 Queen Victoria St., London, E. C.



ORIGINAL BARNES

Positive Feed **Upright Drills**

10 to 50-inch Swing

Send for Drill Catalogue.

W. F. & JNO. BARNES CO.
(*Established* 1872)
1999 Ruby St., Rockford, Ill.

TRADE W.F. and J.B. MARK

The Best Dry Battery for AUTOMOBILE SPARKING

IS THE

Becko Spark Cell

4 Cells $1.25

J. H. BUNNELL & CO.
Electrical Manufacturers 20 Park Place, NEW YORK

If BALDNESS were caused by DISEASE,

A Cure would have long ago been found.

By exercising the arms, we build up muscle—*not* by outside application of medicine. The arms, the body and the lower limps can be exercised at will—but the *scalp* requires mechanical aid. Exercise makes the blood circulate, lack of excercise makes it stagnant. The Vacuum method is the kind of exercise that makes the blood circulate. It gently draws the rich blood to the scalp and feeds the shrunken hair roots. This causes the hair to grow. It is the simple, common-sense principle of physical culture applied to the scalp.

Our Guarantee

(Backed by the Bank):

We will send you by prepaid express, an Evans Vacuum Cap, allowing you ample time to prove its virtue, and all we ask of you is to deposit the price of the appliance in the Jefferson Bank of St. Louis during the trial period, subject to ***your own order.*** If you do not cultivate a sufficient growth of hair to convince you that this method is effective, simply notify the bank and they will return your deposit. ***All orders are sent through the bank. We have no traveling agents or representatives.***

A sixteen-page book, illustrated, will be sent you free.

Evans Vacuum Cap Co.
625 Fullerton Building
St. Louis



SENSITIVE LABORATORY BALANCE.

By N. Monroe Hopkins.—This "built-up" laboratory balance will weigh up to one pound and will turn with a quarter of a postage stamp. The balance can be made by any amateur skilled in the use of tools, and it will work as well as a $125 balance. The article is accompanied by detailed working drawings showing various stages of the work. This article is contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **1184.** Price 10 cents For sale by MUNN & Co., 361 Broadway, New York City, or any bookseller or newsdealer.

Moving Picture Machines



Films, Stereopticons, Views.

If you contemplate going into the public entertainment business, write for catalogue No. 9, which gives information and prices of Moving Picture Machines. Films, Stereopticons and Views. We offer dependable apparatus and views only; no second-hand goods for sale. Send 10 cents in stamps to cover postage of 364 page catalogue.

KLEINE OPTICAL CO.
52 State Street, - - - Chicago, Ill.

læŋgwidʒiz

Catalogs translated and printed. Spanish, Russian, French, German. Linotype Composition Half-tone work.

LANGUAGES PRINTING COMPANY
Languages Building, 15 West 18th St., New York

60 YEARS' EXPERIENCE

PATENTS

TRADE MARKS
DESIGNS
COPYRIGHTS &c.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. HANDBOOK on Patents sent free. Oldest agency for securing patents.

Patents taken through Munn & Co. receive *special notice*, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, $3 a year; four months, $1. Sold by all newsdealers.

MUNN & Co. 361 Broadway, **New York**
Branch Office, 625 F St., Washington, D. C.

Surgical appliance, Breslin & Lees	794,160
Suspension attachment, adjustable, F. L. Gregory	794,671
Swinging seat or hammock, W. S. Bowie	794,484
Switch safety lock, split, Auspos & Nelson	794,155
Syringe, K. Schneyder	794,190
Table lock, pedestal extension, E. Tyden	794,204
Tachometer, G. Saaler	794,426
Tank heater, W. Dixon	794,593
Taping machine, F. A. Sandstrom	794,553
Target, Ford & Whitney	794,601
Telegraphic transmitting apparatus, tape controlled, D. Murray	794,242
Telegraphy and transmission across space, wireless, A. Artom	794,334
Telegraphy, wireless, W. S. Hogg	794,459
Telephone lock-out mechanism, Matheny & Hastings	794,370
Telephone switchboard, M. C. Burt	794,343
Telephone system, W. W. Dean, 794,348, 794,349,	794,702
Thermal cut out, T. Varney	794,435
Thermostat, J. D. Gould	794,497
Threshing and straw cutting machine, C. J. Smith	794,687
Ticket case, R. D'Orn	794,397
Ticket collecting apparatus, H. L. Des Anges	794,217
Ticket, railway cash fare receipt passage, W. C. Pope	794,548
Tie. See Fence tie.	
Timber transferring machine, G. M. Hinkley	794,354
Timber treating apparatus, P. H. Gerhard	794,605
Tire, pneumatic, W. F. Stearns	794,197
Tire, pneumatic, D. J. May	794,372
Tires, machine for manufacturing pneumatic wheel, A. E. Vincent	794,473
Tongs, Dunham & Robinson	794,597
Tool, combination, J. H. Priestley	794,310
Tool, pneumatic, J. C. Campbell	794,586
Toy, educational, H. Robinson	794,466
Trace carrier, J. Kiernan	794,625
Track brake, N. E. Knutzen	794,460
Track switch, overhead, E. Marl	794,367
Tram stops, air valve for safety, H. G. Sedgwick	794,320
Truck, E. J. Simon	794,428
Tubing making machine, C. Thibodeau	794,433
Tunnel erecting apparatus, E. W. Moir	794,635
Tunneling shield, E. D. Wright	794,579
Tunneling shield, E. W. Moir 794,632 to	794,634
Turbine, R. H. Goldsborough, 794,606 to 794,608, 794,610 to	794,615
Turbine and means for governing same, R. H. Goldsborough	794,609
Twisting and waxing machine, thread, A. H. Forsythe	794,669
Type lines, producing justified, O. Mergenthaler	794,629
Typewriter table, G. W. Donning	794,594
Typewriting machine, F. X. Wagner	794,437
Typewriting machine, E. L. Foster	794,494
Typographic machine, Mergenthaler & Lawrenz	794,628
Universal joint mechanism, L. P. Valiquet	794,434
Unloading mechanism, C. R. Maples	794,526
Valise and tent, combined, A. C. M. Finlay	794,351
Valve, J. C. Wills	794,267
Valve, automatic regulating, C. H. Caspar	794,394
Valve gear, W. P. Reynolds	794,642
Valve, pressure reducing and regulating, G. S. Willits	794,651
Valve, pressure regulating, F. C. Few	794,288
Valve, steam engine, T. Dugan	794,596
Vapor burner, C. C. Todd	794,263
Vaporizer, E. W. Ballentine	794,387
Vehicle top, A. M. Beebe	794,446
Vending machine, coin controlled, J. L. Simmons	794,557
Vending machine coin detector, C. Bigelow	794,483
Vertical boiler, T. Suzuki	794,199
Veterinary apparatus, S. T. Bailey	794,480
Voltage regulator, P. M. Lincoln	794,365
Wagon brake coupling, J. E. Smart	794,324
Water screen and filter, S. Stout, et al	794,325
Water tube boiler, G. Y. Bonus	794,338
Watering fountain, stock, J. H. Thornburg	794,326
Web rolls, handling of, H. A. W. Wood	794,577
Weed cutter, E. M. Lambson	794,361
Weed exterminator, M. Schmitt	794,318
Weed turner, W. M. Ellsworth	794,600
Weighing apparatus, W. S. & C. I. Corby	794,215
Wheel. See Car wheel.	
Wheel, J. W. Meixell	794,528
Wheel guard, vehicle, B. E. Thompson	794,472
Window box, knockdown, A. Assorati	794,444
Window screen, W. E. Sherwood 794,469,	794,470
Window ventilator, H. O. Reese	794,251
Wire receptacle, woven, C. S. Baron	794,156
Wrench, B. S. Boggs	794,448
Yoke attachment, neck, L. T. Gucker	794,618
Zinc from ores, removing or recovering, W. Stewart	794,198
Zither bowing device, J. von Peichl	794,544

DESIGNS.

Automobile body, O. E. Barthel	37,491
Badge, C. C. Fearing	37,478
Bodkin, E. S. Simons	37,483
Book mark, E. A. Ekstromer	37,484
Button rim, G. E. Schweig	37,479
Carriage body, C. E. Duryea	37,490
Coin actuated machine casing, A. A. Caille, 37,488,	37,489
Condiment holder, E. C. Hurlbert	37,482
Fabric, textile, J. W. Kemp 37,492,	37,493
Mount, E. S. Cheney	37,481
Sign, cigar dealer's, O. Wurscher	37,486
Sign, jeweler's, O. Wurscher	37,485
Statuette, R. F. Outcault	37,480
Vibrating machines, stand for automatic, M. Borsodi	37,487

LABELS.

"Bestuvall," for sardines, R. Coleman & Co.	12,269
"Bridal Cream Sugar Corn," for sugar corn, Riverton Packing Co.	12,264
"Edmund Hoyle," for cigars, Moeller & Kolb	12,262
"Finest Malort Bitter," for a medicinal liquor, C. A. Zahn Co.	12,260
"Florida East Coast," for canned pineapple, Planters Packing and Preserving Co.	12,265
"Golden Brittle Pop Corn by the Ear," for popcorn, C. M. Waite	12,268
"Golden Crown," for talking machine records, Englewood Co.	12,271
"Indian Maid, Cream Sugar Corn," for sugar corn, Saulsbury Bros.	12,263
"Just Right," for hooks and eyes, Carson, Pirie, Scott and Co.	12,270
"Purity Brand," for dates, J. W. Lumsdon	12,266
"Safe-T-Benzin," for benzin, O. Raubenheimer	12,261
"Salvator, The Triumph of the 20th Century," for medicine, Halpern & Schaffer	12,258
"Surprise," for grapes, I. J. Brokaw	12,267
"Swain's Backache, Kidney and Liver Cure," for medicine, Swain Medicine Co.	12,259

PRINTS.

"E. Olson's Rheumatic Cure Benedictiner Oil," for medicine, E. Olson	1,369
"Eyeglass Attached to Finger of Hand," for eyeglasses, E. B. Meyrowitz	1,372
"Golden Brittle Pop Corn by the Ear," for popcorn, C. M. Waite	1,371
"Good Bread—Good Nature," for flour, Washburn-Crosby Co.	1,370

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

Autocar

Type X
$900



The Runabout That Can Lift 275 Times Its Own Weight

The Autocar Runabout is not a flimsy toy but a *thoroughbred car* built along the lines of the best foreign and American touring cars. *Strong, powerful* and *fast.* It weighs 1200 lbs. and has a motor of ten horse-power—*able to lift 275 times the weight of the car.*

This motor is of the two cylinder opposed type—practically vibrationless. Motor is located *under hood* in front where it is instantly accessible. There are *three* forward speeds and reverse. The car can be run from *3 to 35 miles an hour,* and is a great hill climber. In addition to the above features the Autocar Runabout has *ball bearings,* and *shaft drive.* The price of this car is $900. Our catalogue fully describes and illustrates it together with our Type VIII, four passenger, $1400 car; and our Type XI, four-cylinder, side entrance tonneau, $2000 car. Catalogue and dealer's name free.

THE AUTOCAR COMPANY, Ardmore, Pa.
Member Asso. Licensed Auto. Mfrs.

SAFETY FOR CYCLISTS.

"When cycling do not trouble borrow.
But *brake* yourself with the safe MORROW."



Every wheelman in the country ought to know that the greatest security for himself and his machine is afforded by the attachment of

THE MORROW BRAKE

One clutch—the Forward Drive—only. No increased friction when pedaling. Easily taken apart when necessary. Chief parts are cut from solid steel. Holds the wheel in perfect control so that it can be stopped instantly. Interior parts of brake turn with brake itself when coasting. All parts interchangeable. No friction of interior parts. Price complete **$5.00**. Booklets sent free.

ECLIPSE MACHINE CO. **Elmira, N. Y., U. S. A.**

PATENT OFFICE EXAMINERS WANTED



The position of Assistant Examiner in the Patent Office is the most attractive situation to be secured in the Government service. The entrance salary is $1,200 a year and promotions are rapid, with salaries reaching $2,500. The training in the Patent Office is especially valuable. The examiner secures information of the greatest value to almost every important business. Skilled Patent Office employees are eagerly sought by all large manufacturing concerns in the United States and by Patent Attorneys. This is a choice opportunity to secure a situation paying a good salary and to prepare for the most remunerative positions in industrial life.

A POSITION AND A PROFESSION

Clerks or Examiners in the Patent Office have opportunity to attend one of three of the best regular law schools in the country. All have evening sessions exclusively.

Appointment as Patent Office Examiner is secured through competitive Civil Service examination. Applicants are comparatively few and *practically all* of those who pass are appointed.

The Institute gives the only thorough special preparation to pass this examination provided by any school. Our students have been unusually successful. They have received the highest grades and secured the earliest appointments. We shall gladly furnish proof of this.

WHO SHOULD PREPARE

The examination is open to all over twenty years old, but an applicant should be well grounded in mathematics, physics, technics, chemistry, and German or French. We can then give you a special training course which will insure a high grade. If you are not prepared in any of the subjects named, we can give you additional instruction which will equip you thoroughly. *Do not attempt to pass this examination without special assistance, for the requirements are technical and you would in all probability fail.*

We shall gladly give you, without charge, full information about Patent Office positions, chances of appointment, opportunities for advancement, etc. Address

NATIONAL CORRESPONDENCE INSTITUTE, 66-80 Second National Bank Building, Washington, D. C.

WANTED—Men and boys to learn plumbing trade. Cannot supply demand for graduates. $4 00 to $5 00 per day. Many complete course in two months. Graduates admitted to Union and Master Plumbers Association. Send for free catalogue. COYNE BROS. Co., Plumbing Schools, 239 to 245 Tenth Avenue, New York City, Cincinnati, O., St. Louis, Mo.

WANTED.—Expert Drill Operator, Naval Station, Guantanamo, Cuba. For further information address "Chief of the Bureau of Yards and Docks, Navy Department, Washington, D. C."

SPECIAL MANUFACTURING.
DIES AND STAMPINGS TO ORDER.
SPECIAL MACHINERY-MODELS-EXPERIMENTAL WORK.
DROP FORGING DIES AND DROP FORGINGS.
HARDWARE SPECIALTIES ETC. MANFD. TO ORDER. SEND SAMPLES OR DRAWINGS FOR ESTIMATES. WRITE FOR OUR BOOKLET.
THE GLOBE MACHINE & STAMPING CO.
970 HAMILTON ST., CLEVELAND, OHIO.

ICE MACHINES. Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 899 Clinton St., Milwaukee, Wis.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery.
E. V. BILLAARD, 24 Frankfort Street, New York.

Dies, Tools, Models and Special Machinery. Metal Specialties and Stampings Manufactured.
HOEFT & MOORE, Chicago, U. S. A.
OFFICE, 536 FIFTH AVENUE. WORKS, INDIANA & FRANKLIN STREETS.

BALLOONS Aeronaut L. Stevens, Box 181 Madison Sq., N. Y.

DRYING MACHINES. S. E. WORRELL, Hannibal, Mo.

MODELS CHICAGO MODEL WORKS
ESTABLISHED 1867 179 E. MADISON ST. CHICAGO, ILL.
WRITE FOR CATALOGUE OF MODEL SUPPLIES.

RUBBER Expert Manufacturers Fine Jobbing Work
PARKER, STEARNS & SUTTON, 228-229 South St., New York

INVENTORS' AND MACHINISTS' Machines and Tools designed. Inventions perfected. Accurate drafting. C. H. M'Glehan & Co., 110 W. 34th St., N. Y.

MODELS & GEARS INVENTIONS PERFECTED UNION MODEL WORKS 193 So. CLARK St. CHICAGO.

MODELS dies, boxes, metal stampings, patent articles novelties, manufactured and sold Printing on aluminum. U. S. Novelty Co., Lily Dale, N. Y.

MODEL AND EXPERIMENTAL WORK.
Electrical and Mechanical Instruments. Small Mach'y
EDWARD KLEINSCHMIDT, 82 W. Broadway, New York

ALL KINDS OF
MACHINISTS' TOOLS and SUPPLIES
ST. LOUIS MACHINISTS' SUPPLY CO.
1118 Pine Street - - St. Louis, Mo.
Send for our catalogue

Agents Wanted

in every railway shop to solicit subscriptions for the

Railway Master Mechanic

ONE DOLLAR A YEAR

LIBERAL COMMISSION TO AGENTS

.... ADDRESS ....

Railway Master Mechanic

Security Building CHICAGO — Vanderbilt Building NEW YORK

AUTO STORAGE BATTERIES ALL KINDS
THE WILLARD STORAGE BATTERY CO. CLEVELAND, O.

LEARN WATCHMAKING

Refined, profitable labor. Competent men always in demand. We teach it thoroughly in as many months as it formerly took years. Does away with tedious apprenticeship. Money earned while studying. Positions secured. Easy terms. Send for catalog.
ST. LOUIS WATCHMAKING SCHOOL, St. Louis, Mo.

Learn Telegraphy and R. R. Accounting

$50 to $100 per month salary assured our graduates under bond. You don't pay us until you have a position. Largest system of telegraph schools in America. Endorsed by all railway officials. *Operators always in demand.* Ladies also admitted. Write for catalogue.
MORSE SCHOOL OF TELEGRAPHY
Cincinnati, O., Buffalo, N. Y., Atlanta, Ga., La Crosse, Wis., Texarkana, Tex., San Francisco, Cal.

RADIUM AND THE RADIO-ACTIVE

Substances. No better or clearer scientific account has been published than that contained in SCIENTIFIC AMERICAN SUPPLEMENT **1429.** The paper presents all that is at present known about radium and the radio-active substances. Price 10 cents, by mail. Munn & Co., 361 Broadway, New York City and all newsdealers.

LE PAGE'S MUCILAGE

No gumming to clog neck of bottle—No sediment—will not spoil nor discolor the finest papers. Full 2 oz. bottle retails at 5c., or sent by mail for 10c.; also half-pints, pints and quarts.

LePage's Photo Paste, 2 oz. size retails 5c.; by mail, 10c.

LE PAGE'S GLUE STRONGEST IN THE WORLD
1 oz. bottle or tube, 10c.; by mail, 12c.

RUSSIA CEMENT CO., 139 Essex Ave., Gloucester, Mass.



Orient Surrey, Price, $450

Summer Rides in an Orient Buckboard

Can you think of any better sport? Spinning along at express train speed, in a car so simple a child can run it—no fear of troublesome breakdowns nor tinkering on the road—and the running cost is less than ½ cent a mile.

Orient Buckboards are made in four styles, for two or four passengers, at $375, $450, $475, $525. Orient Touring Cars from $1500 to $2250. Catalogue free if you address Dept. H.

WALTHAM MFG. CO., - - Waltham, Mass.

Members of Association of Licensed Automobile Manufacturers.

To INVESTIGATE



The mechanically correct DURYEA, invariably is to purchase. **Duryeas** are different is the reason. Patented features make them for Comfort and Economy Supreme. Send for leaflet it Tell the Reason Why.

DURYEA POWER CO., 44-84 Aeyrud St., Reading Pa.

THE ROYAL TOURIST



$3,000

32-38 horse power, 2,500 pounds, 4 cylinders, vertical, shaft drive. More Exclusive Features of Merit than any other car in America. Guaranteed Deliveries. Write Dept. M for catalog.

ROYAL MOTOR CAR CO. - Cleveland, Ohio



CHARTER

Stationaries, Portables, Hoisters, Pumpers, Sawing and Boat Outfits, Combined with Dynamos.

Gasoline, Gas, Kerosene.

Send for Catalogue.

State Power Needs.

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

What Is Daus' Tip-Top?



TO PROVE that Daus' "Tip-Top" is the best and simplest device for making **100 copies** from pen-written and **50 copies** from typewritten original, we will ship complete duplicator, cap size, **without deposit,** on **ten (10) days' trial.**

Price $7.50 less trade discount of 33⅓ per cent, or $5 Net

The Felix A. B. Daus Duplicator Co., Daus Bldg., 111 John St., New York

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Safes, Sewing Machines, Bicycles, Tools, etc. save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

Micro Scopes

Our Microscopes, Microtomes, Laboratory Glassware, Chemical Apparatus, Chemicals, Photo Lenses and Shutters, Field Glasses, Projection Apparatus, Photo-Micro Cameras are used by the leading Laboratories and Government Departments Round the World.

Catalogs free.

BAUSCH & LOMB OPT. CO.
ROCHESTER, N.Y.

THE ENGINE THAT PULLS



with a strong, steady pull. Used and recommended by thousands. A postal card with your name and address will bring particulars. Our machines and prices will interest you.

Hagan Gas Engine & Mfg. Co.
Winchester, Ky., U.S.A.

Electrical Engineering

and Experimental Work of Every Description

We have every facility for producing first-class work promptly. Our factory is equipped with modern machinery throughout.

C. F. SPLITDORF
Engineering Dept. 17-27 Vandewater St., N. Y. City

The New Model... Air Gun

Shoots 21-100 Darts and Slugs

37 inches long, 70 ounces weight, with appurtenances 93 ounces. For close shooting and gallery use. Easy to load and fire. Six darts, six targets, 100 slugs included, for **$6.25.**

H. M. QUACKENBUSH, Manufacturer, Herkimer, N. Y



GARDNER DIE STOCK
GOOD GOODS CHEAP
C. H. BESLY & CO CHICAGO ILL. U.S.A.
15 to 21 Clinton Street.

Rambler

This is pre-eminently a family car. Its enjoyment is not confined to the hours when the men of the household are free; *women and children can use it meanwhile.* ¶ Operation is by one lever, pedals and a throttle attached to the steering wheel. ¶ The hand that steers is the hand that controls. ¶ Ignition is automatic.



Main Office and Factory, Kenosha, Wisconsin.
Branches, Boston—Chicago—Philadelphia.
New York Agency, 134 West Thirty-eighth Street.
Representatives in other leading cities.

THOMAS B. JEFFERY & COMPANY

SURREY. TYPE ONE
16 to 18 horse power, $1350
Other models $750, $850, $2000 and $3000. Full information on request.

Science Eliminates the Possibility of a Burnt Tongue

Price $2.00 Postpaid

Pipe weighs one ounce only

Large capacity bowl



Rarefaction—A, B, C
Diffusion—1, 2, 3
Condensation—B
Drainage—A, B
Ventilation—4

$1,000 Guarantee with each Pipe. Endorsed by Physicians

SEND FOR BOOKLET

THE "A.C." PIPE, 807 Times Building, Broadway & 42d St., New York

Jiu-Jitsu Instruction by President Roosevelt's Teacher

JIU-JITSU INSTRUCTION 6c.

NATURE'S WEAPON THAT NEVER FAILS

MAKES SMALL MEN STRONG GIANTS

Japan succeeds because of the physical fitness of her soldiers. They practice Jiu-Jitsu, a system of physical culture which makes them giants of strength and endurance.

P. S.—Send six cents in stamps for FREE instructions

THE AMERICAN COLLEGE OF PHYSICAL CULTURE & JIU-JITSU
378 Boylston Street, Boston, Mass.

20th CENTURY SOAP,

a purely vegetable oil soap, containing no lye, but cleaning by the penetrating nature of its oils. Good for engineers, electricians, chemists, etc., it thoroughly removes all stains, such as rust, grease and oil, either from the hands or clothing, without injuring in the slightest. Also unsurpassed as a **DRILLING SOAP. HAS NO EQUAL FOR AUTOMOBILES.** For cleaning floors and walls, especially hard wood, it is invaluable. Has no equal for automobiles. Does not injure the polish, but adds to the lustre. If your dealer does not keep it, send us his name and address and we will send you a sample can free.

HOFFHEIMER SOAP CO., 169 E. Jackson Boulevard, CHICAGO

Eastern Office, No. 1 Madison Square, NEW YORK. Renshaw Bldg., PITTSBURG, PA.

Washburne's Patent Adjustable "O.K." Paper Fasteners



The neatest and most efficient of the whole "Paper Fastener Tribe."

Attached with the thumb and finger. Absolutely sure. Can be used over again. No points to catch. Lies flat. Will not rust. Made of brass.

Handsome in appearance, and they always work.

Put up in brass boxes of 100 Fasteners each. Ten boxes to a carton. Price **20 cents a box; $1.50 per 1,000,** at all stationers or from the Manufacturer, postage or express prepaid. **Sample box 10 cents.** Illustrated booklet free. Liberal discount to the trade.

JAMES V. WASHBURNE, Mfr.
210 East Genesee St., Syracuse, N. Y.

PRINTING THAT BRINGS RESULTS PAYS YOU

We attend to every detail of Writing, Illustrating, Printing and Binding Booklets. Inventors and manufacturers wishing to sell or exploit their patents can do it very effectively by good circulars and booklets. Estimates furnished. Send 8c. postage for samples and handsome souvenir engraving of St. Louis Exposition, 14x20, on 20x24 paper.

C. L. WRIGHT & CO., 132-4-6 West 14th Street, New York.

COLD GALVANIZING.

AMERICAN PROCESS. NO ROYALTIES.
SAMPLES AND INFORMATION ON APPLICATION.



NICKEL AND Electro-Plating
Apparatus and Material.
THE
Hanson & Van Winkle Co.,
Newark, N. J.
92 William St., N. Y.
30 & 32 S. Canal St.
Chicago.

THE NEW BI-CHROME RIBBON

ON THE



SmithPremier

WRITES RED AND BLACK
(or any other colors)

For Billing, Library Work or Correspondence, the BI-CHROME RIBBON is of immense advantage in accentuating to the eye words or figures desired to be emphatic, or especially noticeable.

INQUIRE ABOUT IT

The Smith Premier Typewriter Co., Syracuse, N.Y.

BRANCH STORES EVERYWHERE

MENNEN'S BORATED TALCUM TOILET POWDER



A Positive Relief For PRICKLY HEAT, CHAFING, and SUNBURN, and all afflictions of the skin.

"A LITTLE HIGHER IN PRICE, PERHAPS, THAN WORTHLESS SUBSTITUTES, BUT A REASON FOR IT."

Removes all odor of perspiration. Delightful after Shaving. Sold everywhere, or mailed on receipt of 25c. Get Mennen's (the original). *Sample Free.*

GERHARD MENNEN COMPANY, Newark, N.J.

The Photoscope



Takes pictures as fast as a person can pose in front of it. Delivers a perfect Photograph, neatly framed and finished, in less than one minute, and will operate regardless of the weather, making as perfect a likeness under the electric light as on a bright sunny day. The only slot machine that produces a perfect photo.

M. S. KLINE
45 N. Division Street, Buffalo, N. Y.

THE EAGLE BRAND

ONION SKIN FINISH CARBON PAPER

is distinctly **a New Invention.** *It's just as clean to handle as a sheet of white paper.* Manifolds like print. Lasts twice as long as ordinary carbon paper. It is made on scientific lines by new and superior machinery. Write for free samples and state whether you use Pen, Pencil or Typewriter Carbon.

AMERICAN RIBBON AND CARBON COMPANY
204 Mill St., Rochester, N. Y., U. S. A.

THE Nulite Vapor GAS Lamps

For Home, Store and Street

We also manufacture Table Lamps, Wall Lamps, Chandeliers, Street Lamps, Etc. 100 Candle Power seven hours ONE CENT. No Wicks. No Smoke. No Odor. Absolutely safe. THEY SELL AT SIGHT. Exclusive territory to good agents. ☞ Write for catalogue and prices.

Chicago Solar Light Co. Dept G, Chicago

JESSOP STEEL Co

MFRS OF CRUCIBLE SHEET STEEL
WASHINGTON, PA.

SAMSON LEATHER TIRE

NON SKIDDING

UNPUNCTURABLE

A. E. GALLIEN, Mgr.

UNITED STATES BRANCHES

NEW YORK 12 West 33d St. | BOSTON 20 Park Square | PHILADELPHIA 1120 Chestnut St.
CHICAGO, 1461 Michigan Boulevard. CLEVELAND, 406 Erie St.